

CE EMC Test Report

Project No. : 1708C277E
Equipment : IP Phone
Brand Name : XonTel
Test Model : XT-22G
Series Model : N/A
Applicant : XonTel Technology Trd. Co. W.L.L
Address : Kuwait City , Qibla , Aladel Tower , F21 , state of Kuwait .
Manufacturer : XonTel Technology Trd. Co. W.L.L
Address : Kuwait City , Qibla , Aladel Tower , F21 , state of Kuwait .
Factory : XonTel Technology Trd. Co. W.L.L
Address : Kuwait City , Qibla , Aladel Tower , F21 , state of Kuwait .
Date of Receipt : Sep. 05, 2017
Apr. 21, 2020
Date of Test : Sep. 05, 2017 ~ Sep. 19, 2017
Issued Date : May 11, 2020
Report Version : R00
Test Sample : Engineering Sample
Standard(s) : EN 55032:2015+AC:2016
EN 61000-3-2:2014
EN 61000-3-3: 2013
EN 55035:2017

The above equipment has been tested and found compliance with the requirement of the relative standards by BTL Inc.

Simon Ling

Prepared by : Simon Ling

Kevin Li

Approved by : Kevin Li

Add: No.3, Jinshagang 1st Road, Shixia, Dalang Town,Dongguan, Guangdong, China.

Tel: +86-769-8318-3000

Web: www.newbtl.com



Certificate #5123.02

Declaration

BTL represents to the client that testing is done in accordance with standard procedures as applicable and that test instruments used has been calibrated with standards traceable to international standard(s) and/or national standard(s).

BTL's reports apply only to the specific samples tested under conditions. It is manufacture's responsibility to ensure that additional production units of this model are manufactured with the identical electrical and mechanical components. **BTL** shall have no liability for any declarations, inferences or generalizations drawn by the client or others from **BTL** issued reports.

The report must not be used by the client to claim product certification, approval, or endorsement by NIST, A2LA, or any agency of the U.S. Government.

This report is the confidential property of the client. As a mutual protection to the clients, the public and ourselves, the test report shall not be reproduced, except in full, without our written approval.

BTL's laboratory quality assurance procedures are in compliance with the **ISO/IEC 17025** requirements, and accredited by the conformity assessment authorities listed in this test report.

BTL is not responsible for the sampling stage, so the results only apply to the sample as received.

The information, data and test plan are provided by manufacturer which may affect the validity of results, so it is manufacturer's responsibility to ensure that the apparatus meets the essential requirements of applied standards and in all the possible configurations as representative of its intended use.

Limitation

For the use of the authority's logo is limited unless the Test Standard(s)/Scope(s)/Item(s) mentioned in this test report is (are) included in the conformity assessment authorities acceptance respective.

Please note that the measurement uncertainty is provided for informational purpose only and are not use in determining the Pass/Fail results.

Table of Contents	Page
REPORT ISSUED HISTORY	6
1 . SUMMARY OF TEST RESULTS	7
1.1 TEST FACILITY	9
1.2 MEASUREMENT UNCERTAINTY	9
2 . GENERAL INFORMATION	11
2.1 GENERAL DESCRIPTION OF EUT	11
2.2 DESCRIPTION OF TEST MODES	12
2.3 EUT OPERATING CONDITIONS	13
2.4 BLOCK DIAGRAM SHOWING THE CONFIGURATION OF SYSTEM TESTED	14
2.5 DESCRIPTION OF SUPPORT UNITS	16
3 . EMC EMISSION TEST	17
3.1 RADIATED EMISSION	17
3.1.1 LIMITS	17
3.1.2 MEASUREMENT INSTRUMENTS LIST	19
3.1.3 TEST PROCEDURE	20
3.1.4 DEVIATION FROM TEST STANDARD	21
3.1.5 TEST SETUP	21
3.1.6 MEASUREMENT DISTANCE	22
3.1.7 TEST RESULTS (UP TO 1 GHZ)	23
3.1.8 TEST RESULTS (ABOVE 1 GHZ)	37
3.2 CONDUCTED EMISSION MEASUREMENT AT AC MAINS POWER PORTS	51
3.2.1 LIMITS	51
3.2.2 MEASUREMENT INSTRUMENTS LIST	51
3.2.3 TEST PROCEDURE	52
3.2.4 DEVIATION FROM TEST STANDARD	52
3.2.5 TEST SETUP	52
3.2.6 TEST RESULTS	53
3.3 ASYMMETRIC MODE CONDUCTED EMISSIONS TEST	61
3.3.1 LIMITS	61
3.3.2 MEASUREMENT INSTRUMENTS LIST	63
3.3.3 TEST PROCEDURE	63
3.3.4 DEVIATION FROM TEST STANDARD	63
3.3.5 TEST SETUP	64
3.3.6 TEST RESULTS	65
3.4 HARMONIC CURRENT EMISSIONS TEST	72
3.4.1 LIMITS	72
3.4.2 MEASUREMENT INSTRUMENTS LIST	72
3.4.3 TEST PROCEDURE	73

Table of Contents	Page
3.4.4 DEVIATION FROM TEST STANDARD	73
3.4.5 TEST SETUP	73
3.4.6 TEST RESULTS	74
3.5 VOLTAGE CHANGES, VOLTAGE FLUCTUATIONS AND FLICKER TEST	77
3.5.1 LIMITS	77
3.5.2 MEASUREMENT INSTRUMENTS LIST	77
3.5.3 TEST PROCEDURE	77
3.5.4 DEVIATION FROM TEST STANDARD	77
3.5.5 TESTSETUP	78
3.5.6 TEST RESULTS	79
4 . EMC IMMUNITY TEST	80
4.1 STANDARD COMPLIANCE/SEVERITY LEVEL/CRITERIA	80
4.2 GENERAL PERFORMANCE CRITERIA	82
4.3 ELECTROSTATIC DISCHARGE IMMUNITY TEST (ESD)	83
4.3.1 TEST SPECIFICATION	83
4.3.2 MEASUREMENT INSTRUMENTS	83
4.3.3 TEST PROCEDURE	83
4.3.4 DEVIATION FROM TEST STANDARD	84
4.3.5 TEST SETUP	84
4.3.6 TEST RESULTS	85
4.4 RADIATED, RADIO-FREQUENCY, ELECTROMAGNETIC FIELD IMMUNITY TEST (RS)	89
4.4.1 TEST SPECIFICATION	89
4.4.2 MEASUREMENT INSTRUMENTS	89
4.4.3 TEST PROCEDURE	89
4.4.4 DEVIATION FROM TEST STANDARD	89
4.4.5 TEST SETUP	90
4.4.6 TEST RESULTS	91
4.5 ELECTRICAL FAST TRANSIENT/BURST IMMUNITY TEST (EFT/BURST)	92
4.5.1 TEST SPECIFICATION	92
4.5.2 MEASUREMENT INSTRUMENTS	92
4.5.3 TEST PROCEDURE	92
4.5.4 DEVIATION FROM TEST STANDARD	92
4.5.5 TEST SETUP	93
4.5.6 TEST RESULTS	94
4.6 SURGE IMMUNITY TEST	95
4.6.1 TEST SPECIFICATION	95
4.6.2 MEASUREMENT INSTRUMENTS	95
4.6.3 TEST PROCEDURE	95
4.6.4 DEVIATION FROM TEST STANDARD	96
4.6.5 TEST SETUP	96
4.6.6 TEST RESULTS	97
4.7 IMMUNITY TO CONDUCTED DISTURBANCES, INDUCED BY RADIO-FREQUENCY	

Table of Contents	Page
FIELDS TEST (CS)	98
4.7.1 TEST SPECIFICATION	98
4.7.2 MEASUREMENT INSTRUMENTS	98
4.7.3 TEST PROCEDURE	98
4.7.4 DEVIATION FROM TEST STANDARD	98
4.7.5 TEST SETUP	99
4.7.6 TEST RESULTS	100
4.8 POWER FREQUENCY MAGNETIC FIELD IMMUNITY TEST (PFMF)	101
4.8.1 TEST SPECIFICATION	101
4.8.2 MEASUREMENT INSTRUMENTS	101
4.8.3 TEST PROCEDURE	101
4.8.4 DEVIATION FROM TEST STANDARD	101
4.8.5 TEST SETUP	102
4.8.6 TEST RESULTS	103
4.9 VOLTAGE DIPS, SHORT INTERRUPTIONS AND VOLTAGE VARIATIONS IMMUNITY TEST	104
4.9.1 TEST SPECIFICATION	104
4.9.2 MEASUREMENT INSTRUMENTS	104
4.9.3 TEST PROCEDURE	104
4.9.4 DEVIATION FROM TEST STANDARD	104
4.9.5 TEST SETUP	104
4.9.6 TEST RESULTS	105
5 . EUT TEST PHOTO	106

REPORT ISSUED HISTORY

Issued No.	Description	Issued Date
R00	Compared with previous report (BTL-EMC-1-1708C277), the product name, brand name, model name, applicant, manufacturer and factory's information are changed which does not affect the test results, the rest are kept the same.	May 11, 2020

Remark: For the original report (BTL-EMC-1-1708C277), the test data, data evaluation and equipment configuration contained was accredited by the Authority of TAF according to the ISO/IEC 17025 quality assessment standard and technical standard(s).

1. SUMMARY OF TEST RESULTS

Test procedures according to the technical standards:

Emission				
Standard(s)	Test Item	Limit	Judgment	Remark
EN 55032: 2015	Radiated emissions up to 1 GHz	Class B	PASS	-----
	Radiated emissions above 1 GHz	Class B	PASS	NOTE (2)
	Radiated emissions from FM receivers	-----	N/A	NOTE (1) NOTE (6)
	Conducted emissions AC mains power port	Class B	PASS	NOTE (7)
	Asymmetric mode conducted emissions	AAN	PASS	NOTE (1) NOTE (8)
		Current Probe	N/A	
		CVP	N/A	
	Conducted differential voltage emissions	-----	N/A	NOTE (1) NOTE (9)

Standard	Test Item	Limit	Judgment	Remark
EN 61000-3-2:2014	Harmonic current emissions	Class A	PASS	NOTE (3)
EN 61000-3-3:2013	Voltage changes, voltage fluctuations and flicker		PASS	

Immunity EN 55024: 2010+A1 :2015				
Section(s)	Test Item	Performance Criterion	Judgment	Remark
EN 61000-4-2:2009	Electrostatic discharge immunity	B	PASS	
EN 61000-4-3: 2006+A1:2008+A2:2010	Radiated, radio-frequency, electromagnetic field immunity	A	PASS	
EN 61000-4-4:2012	Electrical fast transient/burst immunity	B	PASS	
EN 61000-4-5:2014	Surge immunity	B/C	PASS	NOTE (4)
EN 61000-4-6: 2014+AC :2015	Immunity to conducted disturbances, induced by radio-frequency fields	A	PASS	
EN 61000-4-8:2010	Power frequency magnetic field immunity	A	PASS	
EN 61000-4-11:2004	Voltage dips, short interruptions and voltage variations immunity	B / C / C	PASS	NOTE (5)

NOTE:

- (1) "N/A" denotes test is not applicable to this device.
- (2) The EUT's max operating frequency is 166 MHz which exceeds 108 MHz, so the test will be performed.
- (3) If the power consumption is less than 75W, there is no limit applied.
- (4) Performance Criterion C for signal ports and telecommunication ports.
Performance Criterion B for input d.c. power port and a.c. power ports.
- (5) Voltage Dips: >95% reduction – Performance Criterion B
Voltage Dips: 30% reduction – Performance Criterion C
Voltage Interruptions: >95% reduction – Performance Criterion C
- (6) If the EUT has FM function the test will be performed.
- (7) If the EUT has AC power mains port the test will be performed.
- (8)

Cable Type	Number of pairs	Measurement type	Procedures
Balanced Unscreened	1 (2 wire) ;2 (4 wire); 3 (6 wire) ;4 (8 wire)	Voltage	AAN
Balanced Unscreened	See a)	Voltage and Current	CP+CVP
Screened or Coaxial	n/a	Voltage	AAN
Screened or Coaxial	n/a	Voltage or Current	CP or CVP
Unbalanced cables	n/a	Voltage and Current	CP+CVP

Ports connected to cables with more than 4 balanced pairs or where the port is unable to function correctly when connected through an AAN.

- (9) If the EUT has tuner port the test will be performed.
- (10) The requirement followed by the client's specification.

1.1 TEST FACILITY

The test facilities used to collect the test data in this report is at the location of No.3, Jinshagang 1st Road, Shixia, Dalang Town, Dongguan, Guangdong, China.

1.2 MEASUREMENT UNCERTAINTY

Where relevant, the following measurement uncertainty levels have been estimated for tests performed on the EUT as specified in CISPR 16-4-2, The BTL measurement uncertainty is less than the CISPR 16-4-2 U_{CISPR} requirement.

The reported uncertainty of measurement $y \pm U$, where expanded uncertainty U is based on a standard uncertainty multiplied by a coverage factor of $k=2$, providing a level of confidence of approximately 95%.

A. Radiated emissions up to 1 GHz measurement:

Test Site	Method	Measurement Frequency Range	Ant. H / V	U, (dB)
DG-CB02(3m)	CISPR	30MHz ~ 200MHz	V	3.83
		30MHz ~ 200MHz	H	3.79
		200MHz ~ 1,000MHz	V	4.04
		200MHz ~ 1,000MHz	H	4.02

B. Radiated emissions above 1 GHz measurement:

Test Site	Method	Measurement Frequency Range	U, (dB)
DG-CB02(3m)	CISPR	1 ~ 6 GHz	4.50
		6 ~ 18 GHz	5.18

C. Conducted emissions AC mains power port measurement:

Test Site	Method	Measurement Frequency Range	U, (dB)
DG-C01	CISPR	150 kHz ~ 30MHz	3.16

D. Conducted disturbance at telecommunication port measurement:

Test Site	Method	Measurement Frequency Range	U, (dB)
DG-C01	CISPR	AAN 50...40dB	3.76
		AAN 65...50dB	3.76
		AAN 75...60dB	3.76
		Capacitive Voltage Probe	3.04
		RF Current Probe	2.58

E. Harmonic current emissions / Voltage changes, voltage fluctuations and flicker measurement:

Test Site	Method	Measurement Frequency Range	U, (dB)
DG-C01	EN 61000-3-2	Voltage	0.774
	EN 61000-3-3	Current	0.782

F. Immunity Measurement:

Test Site	Method	Measurement Frequency Range	U, (dB)
DG-SR02	EN 61000-4-2	Rise time tr	14.6 %
		Peak current Ip	7.70 %
		Current at 30 ns	7.72 %
		Current at 60 ns	7.72 %
DG-CB05	EN 61000-4-3	80MHz~1GHz, 1GHz~6GHz	2.175 dB
		Electrical measurements	2.267 dB
		Measuring the demodulation on analogue wired network lines	2.267 dB
DG-SR05	EN 61000-4-4	Voltage rise time (tr)	10.4 %
		Voltage peak value(V _p)	8.2 %
		Voltage pulse width(tw)	6.0 %
DG-SR05	EN 61000-4-5	Voltage front time (T _{fv})	5.8 %
		Voltage peak value(V _p)	3.9 %
		Voltage duration(t _d)	0.6 %
DG-CB06	EN 61000-4-6	CDN	3.25 dB
		EM Clamp	4.410 dB
		Electrical measurements	3.258 dB
		measuring the demodulation on analogue wired network lines	3.258 dB
DG-SR05	EN 61000-4-8	Magnetic Field Level	3.787 %
DG-SR05	EN 61000-4-11	voltage fall time (T _f)	2 %

Note: Unless specifically mentioned, the uncertainty of measurement has not been taken into account to declare the compliance or non-compliance to the specification.

2. GENERAL INFORMATION

2.1 GENERAL DESCRIPTION OF EUT

Equipment	IP Phone
Brand Name	XonTel
Test Model	XT-22G
Series Model	N/A
Model Difference	N/A
Power Source	1. Supplied form PoE. 2. DC Voltage supplied from AC/DC adapter. Model: F05L5-050100SPAU L.P.S. Manufacturer: SHENZHEN FRECOM ELECTRONICS CO., LTD
Power Rating	1. DC 48V 2. I/P: 100-240V~ 50/60Hz 0.2A O/P: 5V $\overline{\text{---}}$ 1A
Connecting I/O Port	DC port PC port Internet Port Headphone Port

Note:

1. For a more detailed features description, please refer to the manufacturer's specifications or the user's manual.

2.2 DESCRIPTION OF TEST MODES

To investigate the maximum EMI emission characteristics generates from EUT, the test system was pre-scanning tested base on the consideration of following EUT operation mode or test configuration mode which possible have effect on EMI emission level. Each of these EUT operation mode(s) or test configuration mode(s) mentioned above was evaluated respectively.

Pretest Mode	Description
Mode 1	Headphone
Mode 2	Handset
Mode 3	Headphone
Mode 4	PC Port 1Gbps
Mode 5	PC Port 100Mbps
Mode 6	PC Port 10Mbps
Mode 7	Internet Port 1Gbps
Mode 8	Internet Port 100Mbps
Mode 9	Internet Port 10Mbps

For Radiated Test	
Final Test Mode	Description
Mode 1	Headphone
Mode 2	Handset
Mode 3	Headphone

For Conducted Test	
Final Test Mode	Description
Mode 1	Headphone
Mode 2	Handset
Mode 3	Headphone

For ISN Test	
Final Test Mode	Description
Mode 4	PC Port 1Gbps
Mode 5	PC Port 100Mbps
Mode 6	PC Port 10Mbps
Mode 7	Internet Port 1Gbps
Mode 8	Internet Port 100Mbps
Mode 9	Internet Port 10Mbps

For Harmonics / Flickers Test	
Final Test Mode	Description
Mode 1	Headphone


For EMS Test	
Final Test Mode	Description
Mode 1	Headphone


2.3 EUT OPERATING CONDITIONS

The EUT exercise program used during radiated and/or conducted emission measurement was designed to exercise the various system components in a manner similar to a typical use. The standard test signals and output signal as following:

1. EUT connected to notebook, IP Phone and PoE switch via RJ45 cable.
2. EUT connected to Headphone via RJ9 cable.
3. PoE switch connected to IP Phone and adapter via RJ45&DC cable.

2.4 BLOCK DIAGRAM SHOWING THE CONFIGURATION OF SYSTEM TESTED





2.5 DESCRIPTION OF SUPPORT UNITS

The EUT has been tested as an independent unit together with other necessary accessories or support units. The following support units or accessories were used to form a representative test configuration during the tests.

Item	Equipment	Mfr/Brand	Model/Type No.	Series No.
A	Notebook	Lenovo	G40	YB09261386
B	IP Phone	Xontel	X3SP	1000HF7371004260
C	POE Switch	Xontel	DGS-1008P/Dlink	N/A
D	Adapter	Leader	NU60-F4B0125-I1 NN	N/A
E	Headphone	Xontel	A310QD	N/A

Item	Cable Type	Shielded Type	Ferrite Core	Length
1	RJ11 Cable	NO	NO	1m
2	RJ45 Cable	NO	NO	10m
3	RJ45 Cable	NO	NO	10m
4	DC Cable	NO	NO	1.5m
5	RJ45 Cable	NO	NO	1.8m
6	DC Cable	NO	YES	1.5m
7	AC Cable	NO	NO	1.8m

3. EMC EMISSION TEST

3.1 RADIATED EMISSION

3.1.1 LIMITS

Class A equipment up to 1000MHz

Table clause	Frequency range MHz	Measurement			Class A limits dB(μV/m)
		Facility (see Table A.1)	Distance m	Detector type/ bandwidth	
A2.1	30-230	OATS/SAC	10	Quasi peak / 120 kHz	40
	230-1000				47
A2.2	30-230	OATS/SAC	3		50
	230-1000				57
A2.3	30-230	FAR	10	Quasi peak / 120 kHz	42 to 35
	230-1000				42
A2.4	30-230	FAR	3		52 to 45
	230-1000				52
Apply only A2.1 or A2.2 or A2.3 or A2.4 across the entire frequency range.					

Class A equipment above 1000MHz

Table clause	Frequency range MHz	Measurement			Class A limits dB(μV/m)
		Facility (see Table A.1)	Distance m	Detector type/bandwidth	
A3.1	1000-3000	FSOATS	3	Average / 1 MHz	56
	3000-6000			60	
A3.2	1000-3000			Peak / 1 MHz	76
	3000-6000			80	
Apply A3.1 and A3.2 across the frequency range from 1 000 MHz to the highest required frequency of measurement derived from Table 1.					

Class B equipment up to 1000MHz

B equipment up to 1000MHz					
Table clause	Frequency range MHz	Measurement			Class B limits dB(μV/m)
		Facility (see Table A.1)	Distance m	Detector type/ bandwidth	
A4.1	30-230	OATS/SAC	10	Quasi peak / 120 kHz	30
	230-1000				37
A4.2	30-230	OATS/SAC	3		40
	230-1000				47
A4.3	30-230	FAR	10	Quasi peak / 120 kHz	32 to 25
	230-1000				32
A4.4	30-230	FAR	3		42 to 35
	230-1000				42

Apply only table clause A4.1 or A4.2 or A4.3 or A4.4 across the entire frequency range. These requirements are not applicable to the local oscillator and harmonics frequencies of equipment covered by Table A.6.

Class B equipment above 1000MHz

Table clause	Frequency range MHz	Measurement			Class B limits dB(μV/m)
		Facility (see Table A.1)	Distance m	Detector type/bandwidth	
A5.1	1000-3000	FSOATS	3	Average / 1 MHz	50
	3000-6000				54
A5.2	1000-3000			Peak / 1 MHz	70
	3000-6000				74

Apply A5.1 and A5.2 across the frequency range from 1 000 MHz to the highest required frequency of measurement derived from Table 1.

Notes:

- (1) The limit for radiated test was performed according to as following: EN 55032
- (2) The tighter limit applies at the band edges.
- (3) Emission level (dBuV/m)=20log Emission level (uV/m).
- (4) The test result calculated as following:
Measurement Value = Reading Level + Correct Factor
Correct Factor = Antenna Factor + Cable Loss - Amplifier Gain(if use)
Margin Level = Measurement Value - Limit Value

Required highest frequency for radiated measurement

Highest internal frequency (F_x) MHz	Highest measured frequency MHz
$F_x \leq 108$	1000
$108 < F_x \leq 500$	2000
$500 < F_x \leq 1000$	5000
$F_x > 1000$	5 th up to a maximum 6 GHz,

Note for FM and TV broadcast receiver, F_x is determined from the highest frequency generated or used excluding the local oscillator and tuned frequencies.

3.1.2 MEASUREMENT INSTRUMENTS LIST

Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated until
1	Antenna	Schwarbeck	VULB9160	9160-3232	Mar. 26, 2018
2	Double Ridged Horn Antenna	ARA	DRG-118A	16554	Mar. 26, 2018
3	Amplifier	Agilent	8449B	3008A02274	May. 16, 2018
4	Amplifier	HP	8447D	1937A02847	Feb. 22, 2018
5	RF Pre-selector	Agilent	N9039A	MY46520201	Sep. 03, 2018
6	Cable	emci	LMR-400(30M Hz-1GHz)(10m +2.5m)	N/A	Jun. 26, 2018
7	Cable	emci	EMC104-SM-S M-10000 (1GHz—26.5GHz)(10m)	N/A	Jun. 26, 2018
8	Controller	CT	SC100	N/A	N/A
9	Measurement Software	Farad	EZ-EMC Ver.NB-03A1-0 1	N/A	N/A
10	Spectrum Analyzer	Agilent	E4447A	MY48250208	Sep. 03, 2018

Remark: "N/A" denotes no model name, no serial no. or no calibration specified.

All calibration period of equipment list is one year.


3.1.3 TEST PROCEDURE

- a. The measuring distance of 3 m shall be used for measurements. The EUT was placed on the top of a rotating table 0.8 meter above the ground at a 3 meter semi-anechoic chamber. The table was rotated 360 degrees to determine the position of the highest radiation.(below 1GHz).
- b. The measuring distance of 3 m shall be used for measurements. The EUT was placed on the top of a rotating table 0.8 meter above the ground at a 3 meter semi-anechoic chamber. The table was rotated 360 degrees to determine the position of the highest radiation.(above 1GHz)
- c. The height of the equipment or of the substitution antenna shall be 0.8 m, the height of the test antenna shall vary between 1 m to 4 m. Both horizontal and vertical polarizations of the antenna are set to make the measurement.
- d. The initial step in collecting radiated emission data is a receiver peak detector mode pre-scanning the measurement frequency range. Significant peaks are then marked and then Quasi Peak detector mode re-measured.
- e. All readings are Peak unless otherwise stated QP in column of Note. Peak denotes that the Peak reading compliance with the QP Limits and then QP Mode measurement didn't perform.
(below 1GHz)
- f. All readings are Peak Mode value unless otherwise stated AVG in column of Note. If the Peak Mode Measured value compliance with the Peak Limits and lower than AVG Limits, the EUT shall be deemed to meet both Peak & AVG Limits and then only Peak Mode was measured, but AVG Mode didn't perform. (above 1GHz)
- g. For the actual test configuration, please refer to the related Item - Block Diagram of system tested (please refer to 3.3).


3.1.4 DEVIATION FROM TEST STANDARD

No deviation


3.1.5 TEST SETUP



Note: The antenna can be moved between 1 to 4 meters above the ground.




3.1.6 MEASUREMENT DISTANCE



IEC

Figure C.1 – Measurement distance




IEC

Figure C.2 – Boundary of EUT, Local AE and associated cabling

3.1.7 TEST RESULTS (UP TO 1 GHz)

EUT	IP Phone	Model Name	XT-22G
Temperature	25°C	Relative Humidity	60%
Test Voltage	AC 230V/50Hz	Polarization	Vertical
Test Mode	Headphone		
Note	Adapter		
Test Engineer	Simon Ling		


80 dBuV/m



No.	Freq. MHz	Reading Level dBuV/m	Correct Factor dB	Measure ment dBuV/m	Limit dBuV/m	Margin dB	Detector
1	38.7300	47.75	-12.82	34.93	40.00	-5.07	QP
2	56.1900	44.65	-12.26	32.39	40.00	-7.61	QP
3	125.0600	44.44	-13.35	31.09	40.00	-8.91	QP
4 *	164.8300	47.45	-11.33	36.12	40.00	-3.88	QP
5	894.2700	29.79	2.79	32.58	47.00	-14.42	QP
6	1000.0000	32.03	4.22	36.25	47.00	-10.75	QP

EUT	IP Phone	Model Name	XT-22G
Temperature	25°C	Relative Humidity	60%
Test Voltage	AC 230V/50Hz	Polarization	Horizontal
Test Mode	Headphone		
Note	Adapter		
Test Engineer	Simon Ling		


80 dBuV/m



No.	Freq. MHz	Reading Level dBuV/m	Correct Factor dB	Measure ment dBuV/m	Limit dBuV/m	Margin dB	Detector
1	38.7300	37.70	-12.82	24.88	40.00	-15.12	QP
2 *	163.8600	46.72	-11.38	35.34	40.00	-4.66	QP
3	328.7600	39.05	-9.93	29.12	47.00	-17.88	QP
4	410.2400	42.29	-7.86	34.43	47.00	-12.57	QP
5	700.2700	33.18	-0.93	32.25	47.00	-14.75	QP
6	944.7100	29.51	3.45	32.96	47.00	-14.04	QP

EUT	IP Phone	Model Name	XT-22G
Temperature	25°C	Relative Humidity	60%
Test Voltage	DC 48V	Polarization	Vertical
Test Mode	Headphone		
Note	POE		
Test Engineer	Simon Ling		


80 dBuV/m



No.	Freq. MHz	Reading Level dBuV/m	Correct Factor dB	Measure ment dBuV/m	Limit dBuV/m	Margin dB	Detector
1 *	38.7300	47.39	-12.82	34.57	40.00	-5.43	QP
2	107.6000	43.67	-15.56	28.11	40.00	-11.89	QP
3	163.8600	45.66	-11.38	34.28	40.00	-5.72	QP
4	195.8700	43.99	-11.86	32.13	40.00	-7.87	QP
5	250.1900	45.63	-13.22	32.41	47.00	-14.59	QP
6	494.6300	36.48	-5.86	30.62	47.00	-16.38	QP

EUT	IP Phone	Model Name	XT-22G
Temperature	25°C	Relative Humidity	60%
Test Voltage	DC 48V	Polarization	Horizontal
Test Mode	Headphone		
Note	POE		
Test Engineer	Simon Ling		


80 dBuV/m



No.	Freq. MHz	Reading Level dBuV/m	Correct Factor dB	Measure ment dBuV/m	Limit dBuV/m	Margin dB	Detector
1	44.5500	36.48	-11.95	24.53	40.00	-15.47	QP
2	116.3300	39.12	-14.21	24.91	40.00	-15.09	QP
3	163.8600	45.34	-11.38	33.96	40.00	-6.04	QP
4 *	187.1400	45.86	-11.47	34.39	40.00	-5.61	QP
5	247.2800	51.51	-13.25	38.26	47.00	-8.74	QP
6	399.5700	41.24	-8.12	33.12	47.00	-13.88	QP

EUT	IP Phone	Model Name	XT-22G
Temperature	25°C	Relative Humidity	60%
Test Voltage	AC 230V/50Hz	Polarization	Vertical
Test Mode	Handset		
Note	Adapter		
Test Engineer	Simon Ling		


80 dBuV/m



No.	Freq. MHz	Reading Level dBuV/m	Correct Factor dB	Measure ment dBuV/m	Limit dBuV/m	Margin dB	Detector
1	42.6100	43.61	-12.37	31.24	40.00	-8.76	QP
2	88.2000	46.37	-17.17	29.20	40.00	-10.80	QP
3	125.0600	46.11	-13.35	32.76	40.00	-7.24	QP
4 *	164.8300	47.09	-11.33	35.76	40.00	-4.24	QP
5	206.5399	41.74	-12.75	28.99	40.00	-11.01	QP
6	1000.0000	29.67	4.22	33.89	47.00	-13.11	QP

EUT	IP Phone	Model Name	XT-22G
Temperature	25°C	Relative Humidity	60%
Test Voltage	AC 230V/50Hz	Polarization	Horizontal
Test Mode	Handset		
Note	Adapter		
Test Engineer	Simon Ling		


80 dBuV/m



No.	Freq. MHz	Reading Level dBuV/m	Correct Factor dB	Measure ment dBuV/m	Limit dBuV/m	Margin dB	Detector
1 *	164.8300	47.24	-11.33	35.91	40.00	-4.09	QP
2	220.1200	40.78	-13.53	27.25	40.00	-12.75	QP
3	290.9300	39.24	-11.55	27.69	47.00	-19.31	QP
4	329.7300	39.33	-9.91	29.42	47.00	-17.58	QP
5	410.2400	40.57	-7.86	32.71	47.00	-14.29	QP
6	833.1599	34.94	1.59	36.53	47.00	-10.47	QP

EUT	IP Phone	Model Name	XT-22G
Temperature	25°C	Relative Humidity	60%
Test Voltage	DC 48V	Polarization	Vertical
Test Mode	Handset		
Note	POE		
Test Engineer	Simon Ling		


80 dBuV/m



No.	Freq. MHz	Reading Level dBuV/m	Correct Factor dB	Measure ment dBuV/m	Limit dBuV/m	Margin dB	Detector
1	38.7300	47.22	-12.82	34.40	40.00	-5.60	QP
2 *	163.8600	46.80	-11.38	35.42	40.00	-4.58	QP
3	199.7500	42.23	-12.10	30.13	40.00	-9.87	QP
4	250.1900	43.66	-13.22	30.44	47.00	-16.56	QP
5	500.4500	37.49	-5.73	31.76	47.00	-15.24	QP
6	649.8300	33.84	-2.20	31.64	47.00	-15.36	QP

EUT	IP Phone	Model Name	XT-22G
Temperature	25°C	Relative Humidity	60%
Test Voltage	DC 48V	Polarization	Horizontal
Test Mode	Handset		
Note	POE		
Test Engineer	Simon Ling		


80 dBuV/m



No.	Freq. MHz	Reading Level dBuV/m	Correct Factor dB	Measure ment dBuV/m	Limit dBuV/m	Margin dB	Detector
1	50.3700	36.20	-11.89	24.31	40.00	-15.69	QP
2	114.3900	38.49	-14.50	23.99	40.00	-16.01	QP
3 *	163.8600	46.69	-11.38	35.31	40.00	-4.69	QP
4	184.2300	45.13	-11.45	33.68	40.00	-6.32	QP
5	247.2800	52.04	-13.25	38.79	47.00	-8.21	QP
6	411.2100	43.04	-7.83	35.21	47.00	-11.79	QP

EUT	IP Phone	Model Name	XT-22G
Temperature	25°C	Relative Humidity	60%
Test Voltage	AC 230V/50Hz	Polarization	Vertical
Test Mode	Headphone		
Note	Adapter		
Test Engineer	Simon Ling		


80 dBuV/m



No.	Freq. MHz	Reading Level dBuV/m	Correct Factor dB	Measure ment dBuV/m	Limit dBuV/m	Margin dB	Detector
1	37.7599	42.51	-12.89	29.62	40.00	-10.38	QP
2 *	163.8600	48.02	-11.38	36.64	40.00	-3.36	QP
3	199.7500	40.21	-12.10	28.11	40.00	-11.89	QP
4	329.7300	39.11	-9.91	29.20	47.00	-17.80	QP
5	573.2000	33.49	-4.06	29.43	47.00	-17.57	QP
6	900.0900	29.60	2.90	32.50	47.00	-14.50	QP

EUT	IP Phone	Model Name	XT-22G
Temperature	25°C	Relative Humidity	60%
Test Voltage	AC 230V/50Hz	Polarization	Horizontal
Test Mode	Headphone		
Note	Adapter		
Test Engineer	Simon Ling		


80 dBuV/m



No.	Freq. MHz	Reading Level dBuV/m	Correct Factor dB	Measure ment dBuV/m	Limit dBuV/m	Margin dB	Detector
1	47.4600	30.84	-11.85	18.99	40.00	-21.01	QP
2 *	164.8300	46.70	-11.33	35.37	40.00	-4.63	QP
3	299.6600	38.96	-10.65	28.31	47.00	-18.69	QP
4	327.7900	42.94	-9.95	32.99	47.00	-14.01	QP
5	411.2100	41.22	-7.83	33.39	47.00	-13.61	QP
6	904.9400	31.62	2.96	34.58	47.00	-12.42	QP

EUT	IP Phone	Model Name	XT-22G
Temperature	25°C	Relative Humidity	60%
Test Voltage	AC 110V/60Hz	Polarization	Vertical
Test Mode	Headphone		
Note	Adapter		
Test Engineer	Simon Ling		


80 dBuV/m



No.	Freq. MHz	Reading Level dBuV/m	Correct Factor dB	Measure ment dBuV/m	Limit dBuV/m	Margin dB	Detector
1	37.7599	42.01	-12.89	29.12	40.00	-10.88	QP
2 *	163.8600	47.89	-11.38	36.51	40.00	-3.49	QP
3	199.7500	39.21	-12.10	27.11	40.00	-12.89	QP
4	329.7300	38.61	-9.91	28.70	47.00	-18.30	QP
5	573.2000	32.49	-4.06	28.43	47.00	-18.57	QP
6	900.0900	29.60	2.90	32.50	47.00	-14.50	QP

EUT	IP Phone	Model Name	XT-22G
Temperature	25°C	Relative Humidity	60%
Test Voltage	AC 110V/60Hz	Polarization	Horizontal
Test Mode	Headphone		
Note	Adapter		
Test Engineer	Simon Ling		


80 dBuV/m



No.	Freq. MHz	Reading Level dBuV/m	Correct Factor dB	Measure ment dBuV/m	Limit dBuV/m	Margin dB	Detector
1 *	164.8300	46.20	-11.33	34.87	40.00	-5.13	QP
2	220.1200	38.67	-13.53	25.14	40.00	-14.86	QP
3	299.6600	38.97	-10.65	28.32	47.00	-18.68	QP
4	327.7900	42.44	-9.95	32.49	47.00	-14.51	QP
5	411.2100	40.72	-7.83	32.89	47.00	-14.11	QP
6	904.9400	31.12	2.96	34.08	47.00	-12.92	QP

EUT	IP Phone	Model Name	XT-22G
Temperature	25°C	Relative Humidity	60%
Test Voltage	DC 48V	Polarization	Vertical
Test Mode	Headphone		
Note	POE		
Test Engineer	Simon Ling		


80 dBuV/m



No.	Freq. MHz	Reading Level dBuV/m	Correct Factor dB	Measure ment dBuV/m	Limit dBuV/m	Margin dB	Detector
1	37.7599	47.11	-12.89	34.22	40.00	-5.78	QP
2	58.1300	41.18	-12.81	28.37	40.00	-11.63	QP
3	89.1700	44.73	-17.22	27.51	40.00	-12.49	QP
4 *	163.8600	47.60	-11.38	36.22	40.00	-3.78	QP
5	329.7300	41.16	-9.91	31.25	47.00	-15.75	QP
6	1000.0000	32.72	4.22	36.94	47.00	-10.06	QP

EUT	IP Phone	Model Name	XT-22G
Temperature	25°C	Relative Humidity	60%
Test Voltage	DC 48V	Polarization	Horizontal
Test Mode	Headphone		
Note	POE		
Test Engineer	Simon Ling		

80 dBuV/m




No.	Freq. MHz	Reading Level dBuV/m	Correct Factor dB	Measure ment dBuV/m	Limit dBuV/m	Margin dB	Detector
1	140.5800	42.38	-12.44	29.94	40.00	-10.06	QP
2	164.8300	44.40	-11.33	33.07	40.00	-6.93	QP
3 *	205.5700	47.13	-12.65	34.48	40.00	-5.52	QP
4	256.9800	45.90	-13.47	32.43	47.00	-14.57	QP
5	327.7900	44.47	-9.95	34.52	47.00	-12.48	QP
6	411.2100	41.30	-7.83	33.47	47.00	-13.53	QP

3.1.8 TEST RESULTS (ABOVE 1 GHZ)

EUT	IP Phone	Model Name	XT-22G
Temperature	25°C	Relative Humidity	60%
Test Voltage	AC 230V/50Hz	Polarization	Vertical
Test Mode	Headphone		
Note	Adapter		
Test Engineer	Simon Ling		


80 dBuV/m



No.	Freq. MHz	Reading Level dBuV/m	Correct Factor dB	Measure ment dBuV/m	Limit dBuV/m	Margin dB	Detector
1	1230.0000	45.01	-4.52	40.49	70.00	-29.51	Peak
2	1230.0000	34.30	-4.52	29.78	50.00	-20.22	AVG
3	1755.0000	45.57	-2.44	43.13	70.00	-26.87	Peak
4 *	1755.0000	33.50	-2.44	31.06	50.00	-18.94	AVG
5	3345.0000	37.87	5.03	42.90	74.00	-31.10	Peak
6	3345.0000	26.31	5.03	31.34	54.00	-22.66	AVG
7	3965.0000	36.81	5.60	42.41	74.00	-31.59	Peak
8	3965.0000	25.10	5.60	30.70	54.00	-23.30	AVG
9	5280.0000	35.30	8.40	43.70	74.00	-30.30	Peak
10	5280.0000	24.30	8.40	32.70	54.00	-21.30	AVG
11	5985.0000	34.78	11.03	45.81	74.00	-28.19	Peak
12	5985.0000	23.49	11.03	34.52	54.00	-19.48	AVG

EUT	IP Phone	Model Name	XT-22G
Temperature	25°C	Relative Humidity	60%
Test Voltage	AC 230V/50Hz	Polarization	Horizontal
Test Mode	Headphone		
Note	Adapter		
Test Engineer	Simon Ling		


80 dBuV/m



No.	Freq. MHz	Reading Level dBuV/m	Correct Factor dB	Measure ment dBuV/m	Limit dBuV/m	Margin dB	Detector
1	1070.0000	43.67	-5.19	38.48	70.00	-31.52	Peak
2	1070.0000	31.31	-5.19	26.12	50.00	-23.88	AVG
3	1960.0000	39.70	-1.67	38.03	70.00	-31.97	Peak
4	1960.0000	28.51	-1.67	26.84	50.00	-23.16	AVG
5	2660.0000	38.91	2.11	41.02	70.00	-28.98	Peak
6 *	2660.0000	27.30	2.11	29.41	50.00	-20.59	AVG
7	3250.0000	38.30	4.79	43.09	74.00	-30.91	Peak
8	3250.0000	27.50	4.79	32.29	54.00	-21.71	AVG
9	4770.0000	35.48	6.97	42.45	74.00	-31.55	Peak
10	4770.0000	24.30	6.97	31.27	54.00	-22.73	AVG
11	5550.0000	33.80	9.38	43.18	74.00	-30.82	Peak
12	5550.0000	22.10	9.38	31.48	54.00	-22.52	AVG

EUT	IP Phone	Model Name	XT-22G
Temperature	25°C	Relative Humidity	60%
Test Voltage	DC 48V	Polarization	Vertical
Test Mode	Headphone		
Note	POE		
Test Engineer	Simon Ling		


80 dBuV/m



No.	Freq. MHz	Reading Level dBuV/m	Correct Factor dB	Measure ment dBuV/m	Limit dBuV/m	Margin dB	Detector
1	1230.0000	43.23	-4.52	38.71	70.00	-31.29	Peak
2	1230.0000	33.06	-4.52	28.54	50.00	-21.46	AVG
3	1390.0000	42.38	-3.85	38.53	70.00	-31.47	Peak
4	1390.0000	33.16	-3.85	29.31	50.00	-20.69	AVG
5	2730.0000	38.38	2.53	40.91	70.00	-29.09	Peak
6 *	2730.0000	27.70	2.53	30.23	50.00	-19.77	AVG
7	3260.0000	38.19	4.81	43.00	74.00	-31.00	Peak
8	3260.0000	27.77	4.81	32.58	54.00	-21.42	AVG
9	4750.0000	35.59	6.94	42.53	74.00	-31.47	Peak
10	4750.0000	23.52	6.94	30.46	54.00	-23.54	AVG
11	5740.0000	33.61	10.10	43.71	74.00	-30.29	Peak
12	5740.0000	22.63	10.10	32.73	54.00	-21.27	AVG

EUT	IP Phone	Model Name	XT-22G
Temperature	25°C	Relative Humidity	60%
Test Voltage	DC 48V	Polarization	Horizontal
Test Mode	Headphone		
Note	POE		
Test Engineer	Simon Ling		


80 dBuV/m



No.	Freq. MHz	Reading Level dBuV/m	Correct Factor dB	Measure ment dBuV/m	Limit dBuV/m	Margin dB	Detector
1	1070.0000	42.37	-5.19	37.18	70.00	-32.82	Peak
2	1070.0000	31.11	-5.19	25.92	50.00	-24.08	AVG
3	3080.0000	38.26	4.35	42.61	74.00	-31.39	Peak
4	3080.0000	28.30	4.35	32.65	54.00	-21.35	AVG
5	3270.0000	38.00	4.84	42.84	74.00	-31.16	Peak
6	3270.0000	27.50	4.84	32.34	54.00	-21.66	AVG
7	4845.0000	34.70	7.11	41.81	74.00	-32.19	Peak
8	4845.0000	23.10	7.11	30.21	54.00	-23.79	AVG
9	5290.0000	34.24	8.44	42.68	74.00	-31.32	Peak
10	5290.0000	22.50	8.44	30.94	54.00	-23.06	AVG
11	5905.0000	33.01	10.73	43.74	74.00	-30.26	Peak
12 *	5905.0000	22.30	10.73	33.03	54.00	-20.97	AVG

EUT	IP Phone	Model Name	XT-22G
Temperature	25°C	Relative Humidity	60%
Test Voltage	AC 230V/50Hz	Polarization	Vertical
Test Mode	Handset		
Note	Adapter		
Test Engineer	Simon Ling		


80 dBuV/m



No.	Freq. MHz	Reading Level dBuV/m	Correct Factor dB	Measure ment dBuV/m	Limit dBuV/m	Margin dB	Detector
1	1235.0000	42.95	-4.50	38.45	70.00	-31.55	Peak
2	1235.0000	31.30	-4.50	26.80	50.00	-23.20	AVG
3	2135.0000	39.55	-0.80	38.75	70.00	-31.25	Peak
4	2135.0000	28.30	-0.80	27.50	50.00	-22.50	AVG
5	2905.0000	39.32	3.57	42.89	70.00	-27.11	Peak
6 *	2905.0000	28.50	3.57	32.07	50.00	-17.93	AVG
7	3185.0000	38.76	4.62	43.38	74.00	-30.62	Peak
8	3185.0000	27.51	4.62	32.13	54.00	-21.87	AVG
9	3955.0000	36.67	5.59	42.26	74.00	-31.74	Peak
10	3955.0000	25.11	5.59	30.70	54.00	-23.30	AVG
11	5980.0000	33.86	11.01	44.87	74.00	-29.13	Peak
12	5980.0000	22.30	11.01	33.31	54.00	-20.69	AVG

EUT	IP Phone	Model Name	XT-22G
Temperature	25°C	Relative Humidity	60%
Test Voltage	AC 230V/50Hz	Polarization	Horizontal
Test Mode	Handset		
Note	Adapter		
Test Engineer	Simon Ling		


80 dBuV/m



No.	Freq. MHz	Reading Level dBuV/m	Correct Factor dB	Measure ment dBuV/m	Limit dBuV/m	Margin dB	Detector
1	1155.0000	41.65	-4.83	36.82	70.00	-33.18	Peak
2	1155.0000	30.10	-4.83	25.27	50.00	-24.73	AVG
3	2010.0000	38.69	-1.47	37.22	70.00	-32.78	Peak
4	2010.0000	27.30	-1.47	25.83	50.00	-24.17	AVG
5	2745.0000	37.73	2.62	40.35	70.00	-29.65	Peak
6 *	2745.0000	25.30	2.62	27.92	50.00	-22.08	AVG
7	3175.0000	37.40	4.59	41.99	74.00	-32.01	Peak
8	3175.0000	26.50	4.59	31.09	54.00	-22.91	AVG
9	3785.0000	36.18	5.53	41.71	74.00	-32.29	Peak
10	3785.0000	25.10	5.53	30.63	54.00	-23.37	AVG
11	5475.0000	33.71	9.10	42.81	74.00	-31.19	Peak
12	5475.0000	22.50	9.10	31.60	54.00	-22.40	AVG

EUT	IP Phone	Model Name	XT-22G
Temperature	25°C	Relative Humidity	60%
Test Voltage	DC 48V	Polarization	Vertical
Test Mode	Handset		
Note	POE		
Test Engineer	Simon Ling		


80 dBuV/m



No.	Freq. MHz	Reading Level dBuV/m	Correct Factor dB	Measure ment dBuV/m	Limit dBuV/m	Margin dB	Detector
1	1235.0000	45.11	-4.50	40.61	70.00	-29.39	Peak
2	1235.0000	33.50	-4.50	29.00	50.00	-21.00	AVG
3	2475.0000	39.11	1.02	40.13	70.00	-29.87	Peak
4 *	2475.0000	28.30	1.02	29.32	50.00	-20.68	AVG
5	3085.0000	38.10	4.36	42.46	74.00	-31.54	Peak
6	3085.0000	27.10	4.36	31.46	54.00	-22.54	AVG
7	3865.0000	36.88	5.56	42.44	74.00	-31.56	Peak
8	3865.0000	25.30	5.56	30.86	54.00	-23.14	AVG
9	4780.0000	36.24	6.99	43.23	74.00	-30.77	Peak
10	4780.0000	25.50	6.99	32.49	54.00	-21.51	AVG
11	5560.0000	34.30	9.42	43.72	74.00	-30.28	Peak
12	5560.0000	23.11	9.42	32.53	54.00	-21.47	AVG

EUT	IP Phone	Model Name	XT-22G
Temperature	25°C	Relative Humidity	60%
Test Voltage	DC 48V	Polarization	Horizontal
Test Mode	Handset		
Note	POE		
Test Engineer	Simon Ling		


80 dBuV/m



No.	Freq. MHz	Reading Level dBuV/m	Correct Factor dB	Measure ment dBuV/m	Limit dBuV/m	Margin dB	Detector
1	1070.0000	43.84	-5.19	38.65	70.00	-31.35	Peak
2	1070.0000	32.11	-5.19	26.92	50.00	-23.08	AVG
3	1795.0000	39.43	-2.29	37.14	70.00	-32.86	Peak
4	1795.0000	28.30	-2.29	26.01	50.00	-23.99	AVG
5	3445.0000	37.28	5.29	42.57	74.00	-31.43	Peak
6	3445.0000	25.80	5.29	31.09	54.00	-22.91	AVG
7	3875.0000	36.21	5.57	41.78	74.00	-32.22	Peak
8	3875.0000	25.29	5.57	30.86	54.00	-23.14	AVG
9	5380.0000	34.84	8.76	43.60	74.00	-30.40	Peak
10	5380.0000	23.11	8.76	31.87	54.00	-22.13	AVG
11	5635.0000	34.56	9.71	44.27	74.00	-29.73	Peak
12 *	5635.0000	23.49	9.71	33.20	54.00	-20.80	AVG

EUT	IP Phone	Model Name	XT-22G
Temperature	25°C	Relative Humidity	60%
Test Voltage	AC 230V/50Hz	Polarization	Vertical
Test Mode	Headphone		
Note	Adapter		
Test Engineer	Simon Ling		


80 dBuV/m



No.	Freq. MHz	Reading Level dBuV/m	Correct Factor dB	Measure ment dBuV/m	Limit dBuV/m	Margin dB	Detector
1	1390.0000	42.36	-3.85	38.51	70.00	-31.49	Peak
2	1390.0000	32.10	-3.85	28.25	50.00	-21.75	AVG
3	1750.0000	45.76	-2.46	43.30	70.00	-26.70	Peak
4 *	1750.0000	34.50	-2.46	32.04	50.00	-17.96	AVG
5	2565.0000	38.73	1.54	40.27	70.00	-29.73	Peak
6	2565.0000	27.30	1.54	28.84	50.00	-21.16	AVG
7	3350.0000	37.83	5.05	42.88	74.00	-31.12	Peak
8	3350.0000	26.50	5.05	31.55	54.00	-22.45	AVG
9	4525.0000	36.08	6.53	42.61	74.00	-31.39	Peak
10	4525.0000	25.30	6.53	31.83	54.00	-22.17	AVG
11	5620.0000	34.51	9.65	44.16	74.00	-29.84	Peak
12	5620.0000	23.10	9.65	32.75	54.00	-21.25	AVG

EUT	IP Phone	Model Name	XT-22G
Temperature	25°C	Relative Humidity	60%
Test Voltage	AC 230V/50Hz	Polarization	Horizontal
Test Mode	Headphone		
Note	Adapter		
Test Engineer	Simon Ling		


80 dBuV/m



No.	Freq. MHz	Reading Level dBuV/m	Correct Factor dB	Measure ment dBuV/m	Limit dBuV/m	Margin dB	Detector
1	1750.0000	48.05	-2.46	45.59	70.00	-24.41	Peak
2 *	1750.0000	36.80	-2.46	34.34	50.00	-15.66	AVG
3	2570.0000	38.20	1.57	39.77	70.00	-30.23	Peak
4	2570.0000	26.80	1.57	28.37	50.00	-21.63	AVG
5	3265.0000	38.34	4.83	43.17	74.00	-30.83	Peak
6	3265.0000	26.30	4.83	31.13	54.00	-22.87	AVG
7	3425.0000	38.12	5.24	43.36	74.00	-30.64	Peak
8	3425.0000	27.50	5.24	32.74	54.00	-21.26	AVG
9	4645.0000	35.68	6.75	42.43	74.00	-31.57	Peak
10	4645.0000	24.30	6.75	31.05	54.00	-22.95	AVG
11	5660.0000	34.11	9.80	43.91	74.00	-30.09	Peak
12	5660.0000	23.10	9.80	32.90	54.00	-21.10	AVG

EUT	IP Phone	Model Name	XT-22G
Temperature	25°C	Relative Humidity	60%
Test Voltage	AC 110V/60Hz	Polarization	Vertical
Test Mode	Headphone		
Note	Adapter		
Test Engineer	Simon Ling		


80 dBuV/m



No.	Freq. MHz	Reading Level dBuV/m	Correct Factor dB	Measure ment dBuV/m	Limit dBuV/m	Margin dB	Detector
1	1240.0000	42.58	-4.48	38.10	70.00	-31.90	Peak
2	1240.0000	31.29	-4.48	26.81	50.00	-23.19	AVG
3	1750.0000	45.26	-2.46	42.80	70.00	-27.20	Peak
4 *	1750.0000	35.30	-2.46	32.84	50.00	-17.16	AVG
5	2985.0000	37.19	4.05	41.24	70.00	-28.76	Peak
6	2985.0000	26.50	4.05	30.55	50.00	-19.45	AVG
7	3700.0000	37.01	5.51	42.52	74.00	-31.48	Peak
8	3700.0000	25.79	5.51	31.30	54.00	-22.70	AVG
9	4525.0000	35.58	6.53	42.11	74.00	-31.89	Peak
10	4525.0000	24.30	6.53	30.83	54.00	-23.17	AVG
11	5620.0000	34.51	9.65	44.16	74.00	-29.84	Peak
12	5620.0000	23.10	9.65	32.75	54.00	-21.25	AVG

EUT	IP Phone	Model Name	XT-22G
Temperature	25°C	Relative Humidity	60%
Test Voltage	AC 110V/60Hz	Polarization	Horizontal
Test Mode	Headphone		
Note	Adapter		
Test Engineer	Simon Ling		


80 dBuV/m



No.	Freq. MHz	Reading Level dBuV/m	Correct Factor dB	Measure ment dBuV/m	Limit dBuV/m	Margin dB	Detector
1	1750.0000	46.05	-2.46	43.59	70.00	-26.41	Peak
2 *	1750.0000	35.30	-2.46	32.84	50.00	-17.16	AVG
3	2640.0000	39.05	1.99	41.04	70.00	-28.96	Peak
4	2640.0000	28.50	1.99	30.49	50.00	-19.51	AVG
5	3200.0000	37.64	4.66	42.30	74.00	-31.70	Peak
6	3200.0000	25.30	4.66	29.96	54.00	-24.04	AVG
7	3425.0000	38.12	5.24	43.36	74.00	-30.64	Peak
8	3425.0000	27.30	5.24	32.54	54.00	-21.46	AVG
9	5095.0000	35.40	7.73	43.13	74.00	-30.87	Peak
10	5095.0000	24.11	7.73	31.84	54.00	-22.16	AVG
11	5920.0000	33.89	10.79	44.68	74.00	-29.32	Peak
12	5920.0000	22.50	10.79	33.29	54.00	-20.71	AVG

EUT	IP Phone	Model Name	XT-22G
Temperature	25°C	Relative Humidity	60%
Test Voltage	DC 48V	Polarization	Vertical
Test Mode	Headphone		
Note	POE		
Test Engineer	Simon Ling		


80 dBuV/m



No.	Freq. MHz	Reading Level dBuV/m	Correct Factor dB	Measure ment dBuV/m	Limit dBuV/m	Margin dB	Detector
1	1335.0000	40.32	-4.08	36.24	70.00	-33.76	Peak
2	1335.0000	29.29	-4.08	25.21	50.00	-24.79	AVG
3	2105.0000	37.99	-0.96	37.03	70.00	-32.97	Peak
4	2105.0000	26.50	-0.96	25.54	50.00	-24.46	AVG
5	3000.0000	38.28	4.14	42.42	70.00	-27.58	Peak
6 *	3000.0000	27.10	4.14	31.24	50.00	-18.76	AVG
7	3425.0000	36.74	5.24	41.98	74.00	-32.02	Peak
8	3425.0000	25.30	5.24	30.54	54.00	-23.46	AVG
9	4875.0000	34.83	7.16	41.99	74.00	-32.01	Peak
10	4875.0000	23.10	7.16	30.26	54.00	-23.74	AVG
11	5440.0000	34.42	8.98	43.40	74.00	-30.60	Peak
12	5440.0000	22.50	8.98	31.48	54.00	-22.52	AVG

EUT	IP Phone	Model Name	XT-22G
Temperature	25°C	Relative Humidity	60%
Test Voltage	DC 48V	Polarization	Horizontal
Test Mode	Headphone		
Note	POE		
Test Engineer	Simon Ling		

80 dBuV/m



No.	Freq. MHz	Reading Level dBuV/m	Correct Factor dB	Measure ment dBuV/m	Limit dBuV/m	Margin dB	Detector
1	1510.0000	40.02	-3.36	36.66	70.00	-33.34	Peak
2	1510.0000	29.30	-3.36	25.94	50.00	-24.06	AVG
3	2060.0000	38.49	-1.20	37.29	70.00	-32.71	Peak
4	2060.0000	27.50	-1.20	26.30	50.00	-23.70	AVG
5	2720.0000	38.48	2.47	40.95	70.00	-29.05	Peak
6 *	2720.0000	27.30	2.47	29.77	50.00	-20.23	AVG
7	3180.0000	37.95	4.61	42.56	74.00	-31.44	Peak
8	3180.0000	25.80	4.61	30.41	54.00	-23.59	AVG
9	3965.0000	36.05	5.60	41.65	74.00	-32.35	Peak
10	3965.0000	25.30	5.60	30.90	54.00	-23.10	AVG
11	5375.0000	34.33	8.74	43.07	74.00	-30.93	Peak
12	5375.0000	23.11	8.74	31.85	54.00	-22.15	AVG

3.2 CONDUCTED EMISSION MEASUREMENT AT AC MAINS POWER PORTS

3.2.1 LIMITS

Requirements for conducted emissions from AC mains power ports of Class A equipment

Requirements for conducted emissions from A/C mains power ports of Class A equipment				
Table clause	Frequency Range MHz	Coupling Device	Detector Type / bandwidth	Class A Limits (dB(μV))
A9.1	0.15 - 0.5	AMN	Quasi Peak / 9 kHz	79
	0.5 - 30			73
A9.2	0.15 - 0.5	AMN	Average / 9 kHz	66
	0.5 - 30			60
Apply A9.1 and A9.2 across the entire frequency range.				

Requirements for conducted emissions from AC mains power ports of Class B equipment

Requirements for conducted emissions from AC mains power ports of Class B equipment				
Table clause	Frequency Range MHz	Coupling Device	Detector Type / bandwidth	Class B Limits (dB(μV))
A10.1	0.15 - 0.5	AMN	Quasi Peak / 9 kHz	66-56
	0.5 - 5			56
	5 - 30			60
A10.2	0.15 - 0.5	AMN	Average / 9 kHz	56-46
	0.5 - 5			46
	5 - 30			50
Apply A10.1 and A10.2 across the entire frequency range.				

NOTE:

(1) The test result calculated as following:

Measurement Value = Reading Level + Correct Factor

Correct Factor = Insertion Loss + Cable Loss + Attenuator Factor(if use)

Margin Level = Measurement Value – Limit Value

3.2.2 MEASUREMENT INSTRUMENTS LIST

Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated until
1	Measurement Software	Farad	EZ-EMC Ver.NB-03A1-01	N/A	N/A
2	50Ω Terminator	SHX	TF2-3G-A	08122901	Mar. 26, 2018
3	TWO-LINE V-NETWORK	R&S	ENV216	100526	Mar. 26, 2018
4	EMI Test Receiver	R&S	ESR3	101862	Aug. 15, 2018
5	Artificial-Mains Network	SCHWARZBECK	NSLK 8127	8127685	Aug. 20, 2018
6	Cable	N/A	RG400 12m	N/A	Mar. 07, 2018

Remark: "N/A" denotes no model name, no serial no. or no calibration specified.

All calibration period of equipment list is one year.


3.2.3 TEST PROCEDURE

- The EUT was placed 0.8 meters from the horizontal ground plane with EUT being connected to the power mains through a line impedance stabilization network (LISN). All other support equipments powered from additional LISN(s). The LISN provide 50 Ohm/ 50uH of coupling impedance for the measuring instrument.
- Interconnecting cables that hang closer than 40 cm to the ground plane shall be folded back and forth in the center forming a bundle 30 to 40 cm long.
- I/O cables that are not connected to a peripheral shall be bundled in the center. The end of the cable may be terminated, if required, using the correct terminating impedance. The overall length shall not exceed 1 m.
- LISN at least 80 cm from nearest part of EUT chassis.
- For the actual test configuration, please refer to the related Item –EUT Test Photos.

3.2.4 DEVIATION FROM TEST STANDARD


No deviation

3.2.5 TEST SETUP




3.2.6 TEST RESULTS

EUT	IP Phone	Model Name	XT-22G
Temperature	25°C	Relative Humidity	53%
Test Voltage	AC 230V/50Hz	Phase	Line
Test Mode	Headphone		
Note	Adapter		
Test Engineer	Simon Ling		



No.	Freq. MHz	Reading Level dBuV	Correct Factor dB	Measure ment dBuV	Limit dBuV	Margin dB	Detector
1	0.1680	31.77	9.78	41.55	65.06	-23.51	QP
2	0.1680	21.30	9.78	31.08	55.06	-23.98	AVG
3	0.1905	31.70	9.77	41.47	64.01	-22.54	QP
4	0.1905	21.10	9.77	30.87	54.01	-23.14	AVG
5	0.2490	30.48	9.76	40.24	61.79	-21.55	QP
6	0.2490	19.60	9.76	29.36	51.79	-22.43	AVG
7	0.3390	28.77	9.78	38.55	59.23	-20.68	QP
8	0.3390	18.50	9.78	28.28	49.23	-20.95	AVG
9 *	0.4515	33.49	9.80	43.29	56.85	-13.56	QP
10	0.4515	22.70	9.80	32.50	46.85	-14.35	AVG
11	0.8250	26.81	9.83	36.64	56.00	-19.36	QP
12	0.8250	16.90	9.83	26.73	46.00	-19.27	AVG


EUT	IP Phone	Model Name	XT-22G
Temperature	25°C	Relative Humidity	53%
Test Voltage	AC 230V/50Hz	Phase	Neutral
Test Mode	Headphone		
Note	Adapter		
Test Engineer	Simon Ling		



No.	Freq. MHz	Reading Level dBuV	Correct Factor dB	Measure ment dBuV	Limit dBuV	Margin dB	Detector
1	0.1635	31.70	9.68	41.38	65.28	-23.90	QP
2	0.1635	21.30	9.68	30.98	55.28	-24.30	AVG
3	0.3390	29.97	9.69	39.66	59.23	-19.57	QP
4	0.3390	19.41	9.69	29.10	49.23	-20.13	AVG
5 *	0.4515	37.36	9.69	47.05	56.85	-9.80	QP
6	0.4515	26.91	9.69	36.60	46.85	-10.25	AVG
7	0.8205	30.43	9.72	40.15	56.00	-15.85	QP
8	0.8205	19.50	9.72	29.22	46.00	-16.78	AVG
9	1.4415	30.02	9.78	39.80	56.00	-16.20	QP
10	1.4415	19.60	9.78	29.38	46.00	-16.62	AVG
11	1.9905	29.99	9.85	39.84	56.00	-16.16	QP
12	1.9905	19.50	9.85	29.35	46.00	-16.65	AVG


EUT	IP Phone	Model Name	XT-22G
Temperature	25°C	Relative Humidity	53%
Test Voltage	AC 230V/50Hz	Phase	Line
Test Mode	Handset		
Note	Adapter		
Test Engineer	Simon Ling		

80 dBuV




No.	Freq. MHz	Reading Level dBuV	Correct Factor dB	Measure ment dBuV	Limit dBuV	Margin dB	Detector
1	0.1635	31.80	9.78	41.58	65.28	-23.70	QP
2	0.1635	20.60	9.78	30.38	55.28	-24.90	AVG
3	0.1815	30.93	9.77	40.70	64.42	-23.72	QP
4	0.1815	21.50	9.77	31.27	54.42	-23.15	AVG
5	0.2220	30.43	9.76	40.19	62.74	-22.55	QP
6	0.2220	19.30	9.76	29.06	52.74	-23.68	AVG
7 *	0.4560	33.60	9.80	43.40	56.77	-13.37	QP
8	0.4560	22.70	9.80	32.50	46.77	-14.27	AVG
9	0.8475	26.41	9.83	36.24	56.00	-19.76	QP
10	0.8475	15.90	9.83	25.73	46.00	-20.27	AVG
11	1.9815	25.81	9.92	35.73	56.00	-20.27	QP
12	1.9815	14.20	9.92	24.12	46.00	-21.88	AVG

EUT	IP Phone	Model Name	XT-22G
Temperature	25°C	Relative Humidity	53%
Test Voltage	AC 230V/50Hz	Phase	Neutral
Test Mode	Handset		
Note	Adapter		
Test Engineer	Simon Ling		




No.	Freq. MHz	Reading Level dBuV	Correct Factor dB	Measure ment dBuV	Limit dBuV	Margin dB	Detector
1	0.3435	30.21	9.70	39.91	59.12	-19.21	QP
2	0.3435	19.80	9.70	29.50	49.12	-19.62	AVG
3	0.4515	37.12	9.69	46.81	56.85	-10.04	QP
4 *	0.4515	27.21	9.69	36.90	46.85	-9.95	AVG
5	0.8610	30.02	9.73	39.75	56.00	-16.25	QP
6	0.8610	19.31	9.73	29.04	46.00	-16.96	AVG
7	1.4280	29.96	9.78	39.74	56.00	-16.26	QP
8	1.4280	19.50	9.78	29.28	46.00	-16.72	AVG
9	1.9455	30.11	9.84	39.95	56.00	-16.05	QP
10	1.9455	20.61	9.84	30.45	46.00	-15.55	AVG
11	3.1245	28.87	9.91	38.78	56.00	-17.22	QP
12	3.1245	18.69	9.91	28.60	46.00	-17.40	AVG

EUT	IP Phone	Model Name	XT-22G
Temperature	25°C	Relative Humidity	53%
Test Voltage	AC 230V/50Hz	Phase	Line
Test Mode	Headphone		
Note	Adapter		
Test Engineer	Simon Ling		




No.	Freq. MHz	Reading Level dBuV	Correct Factor dB	Measure ment dBuV	Limit dBuV	Margin dB	Detector
1	0.1815	31.54	9.77	41.31	64.42	-23.11	QP
2	0.1815	21.40	9.77	31.17	54.42	-23.25	AVG
3	0.2310	30.67	9.76	40.43	62.41	-21.98	QP
4	0.2310	20.50	9.76	30.26	52.41	-22.15	AVG
5	0.3480	28.64	9.79	38.43	59.01	-20.58	QP
6	0.3480	18.20	9.79	27.99	49.01	-21.02	AVG
7 *	0.4560	33.61	9.80	43.41	56.77	-13.36	QP
8	0.4560	23.20	9.80	33.00	46.77	-13.77	AVG
9	0.8654	26.49	9.84	36.33	56.00	-19.67	QP
10	0.8654	15.90	9.84	25.74	46.00	-20.26	AVG
11	3.1380	25.86	10.00	35.86	56.00	-20.14	QP
12	3.1380	15.30	10.00	25.30	46.00	-20.70	AVG

EUT	IP Phone	Model Name	XT-22G
Temperature	25°C	Relative Humidity	53%
Test Voltage	AC 230V/50Hz	Phase	Neutral
Test Mode	Headphone		
Note	Adapter		
Test Engineer	Simon Ling		




No.	Freq. MHz	Reading Level dBuV	Correct Factor dB	Measure ment dBuV	Limit dBuV	Margin dB	Detector
1	0.4515	36.96	9.69	46.65	56.85	-10.20	QP
2 *	0.4515	27.51	9.69	37.20	46.85	-9.65	AVG
3	0.8295	30.43	9.73	40.16	56.00	-15.84	QP
4	0.8295	20.79	9.73	30.52	46.00	-15.48	AVG
5	1.4460	30.49	9.78	40.27	56.00	-15.73	QP
6	1.4460	21.30	9.78	31.08	46.00	-14.92	AVG
7	1.9815	29.90	9.85	39.75	56.00	-16.25	QP
8	1.9815	18.60	9.85	28.45	46.00	-17.55	AVG
9	2.5215	29.11	9.87	38.98	56.00	-17.02	QP
10	2.5215	17.90	9.87	27.77	46.00	-18.23	AVG
11	3.0885	28.55	9.90	38.45	56.00	-17.55	QP
12	3.0885	17.40	9.90	27.30	46.00	-18.70	AVG

EUT	IP Phone	Model Name	XT-22G
Temperature	25°C	Relative Humidity	53%
Test Voltage	AC 110V/60Hz	Phase	Line
Test Mode	Headphone		
Note	Adapter		
Test Engineer	Simon Ling		



No.	Freq. MHz	Reading Level dBuV	Correct Factor dB	Measure ment dBuV	Limit dBuV	Margin dB	Detector
1	0.1545	35.08	9.79	44.87	65.75	-20.88	QP
2	0.1545	24.70	9.79	34.49	55.75	-21.26	AVG
3	0.1680	33.63	9.78	43.41	65.06	-21.65	QP
4	0.1680	23.10	9.78	32.88	55.06	-22.18	AVG
5	0.1815	33.42	9.77	43.19	64.42	-21.23	QP
6	0.1815	20.80	9.77	30.57	54.42	-23.85	AVG
7	0.3975	28.03	9.79	37.82	57.91	-20.09	QP
8	0.3975	17.40	9.79	27.19	47.91	-20.72	AVG
9 *	0.4605	33.97	9.80	43.77	56.68	-12.91	QP
10	0.4605	23.60	9.80	33.40	46.68	-13.28	AVG
11	19.6440	24.78	10.65	35.43	60.00	-24.57	QP
12	19.6440	14.89	10.65	25.54	50.00	-24.46	AVG

EUT	IP Phone	Model Name	XT-22G
Temperature	25°C	Relative Humidity	53%
Test Voltage	AC 110V/60Hz	Phase	Neutral
Test Mode	Headphone		
Note	Adapter		
Test Engineer	Simon Ling		



No.	Freq. MHz	Reading Level dBuV	Correct Factor dB	Measure ment dBuV	Limit dBuV	Margin dB	Detector
1	0.1545	33.85	9.68	43.53	65.75	-22.22	QP
2	0.1545	23.40	9.68	33.08	55.75	-22.67	AVG
3	0.1770	32.13	9.68	41.81	64.63	-22.82	QP
4	0.1770	21.80	9.68	31.48	54.63	-23.15	AVG
5	0.4065	27.99	9.68	37.67	57.72	-20.05	QP
6	0.4065	17.90	9.68	27.58	47.72	-20.14	AVG
7 *	0.4560	36.99	9.69	46.68	56.77	-10.09	QP
8	0.4560	26.31	9.69	36.00	46.77	-10.77	AVG
9	1.2075	26.11	9.75	35.86	56.00	-20.14	QP
10	1.2075	15.60	9.75	25.35	46.00	-20.65	AVG
11	2.5395	25.82	9.87	35.69	56.00	-20.31	QP
12	2.5395	15.30	9.87	25.17	46.00	-20.83	AVG

3.3 ASYMMETRIC MODE CONDUCTED EMISSIONS TEST

3.3.1 LIMITS

Requirements for asymmetric mode conducted emissions from Class A equipment

Table clause	Frequency range MHz	Coupling device	Detector type / Bandwidth	Class A voltage limits dB(μV)	Class A current limits dB(μV)
A11.1	0.15 — 0.5	AAN	Quasi Peak / 9 kHz	97 — 87	n/a
	0.5 — 30			87	
	0.15 — 0.5	AAN	Average / 9 kHz	84— 74	
	0.5 — 30			74	
A11.2	0.15 — 0.5	CVP and current probe	Quasi Peak / 9 kHz	97 — 87	53 — 43
	0.5 — 30			87	43
	0.15 — 0.5	CVP and current probe	Average / 9 kHz	84— 74	40 — 30
	0.5 — 30			74	30
A11.3	0.15 — 0.5	Current probe	Quasi Peak / 9 kHz	n/a	53 — 43
	0.5 — 30				43
	0.15 — 0.5	Current probe	Average / 9 kHz		40 — 30
	0.5 — 30				30

The choice of coupling device and measurement procedure is defined in Annex C.

AC mains ports that also have the function of a wired network port shall meet the limits given in Table A.9. The measurement shall cover the entire frequency range.

The application of the voltage and/or current limits is dependent on the measurement procedure used. Refer to Table C.1 for applicability.

Testing is required at only one EUT supply voltage and frequency.

Applicable to ports listed above and intended to connect to cables longer than 3 m.

Requirements for asymmetric mode conducted emissions from Class B equipment

Table clause	Frequency range MHz	Coupling device	Detector type / Bandwidth	Class B voltage limits dB(μV)	Class B current limits dB(μV)
A12.1	0.15 — 0.5	AAN	Quasi Peak / 9 kHz	84 — 74	n/a
	0.5 — 30			74	
	0.15 — 0.5	AAN	Average / 9 kHz	74— 64	
	0.5 — 30			64	
A12.2	0.15 — 0.5	CVP and current probe	Quasi Peak / 9 kHz	84 — 74	40 —30
	0.5 — 30			74	30
	0.15 — 0.5	CVP and current probe	Average / 9 kHz	74— 64	30 —20
	0.5 — 30			64	20
A12.3	0.15 — 0.5	Current probe	Quasi Peak / 9 kHz	n/a	40 —30
	0.5 — 30				30
	0.15 — 0.5	Current probe	Average / 9 kHz		30 —20
	0.5 — 30				20

The choice of coupling device and measurement procedure is defined in Annex C.

Screened ports including TV broadcast receiver tuner ports are measured with a common-mode impedance of 150 Ω . This is typically accomplished with the screen terminated by 150 Ω to earth.

AC mains ports that also have the function of a wired network port shall meet the limits given in Table A.10.

The measurement shall cover the entire frequency range.

The application of the voltage and/or current limits is dependent on the measurement procedure used. Refer to Table C.1 for applicability.

Measurement is required at only one EUT supply voltage and frequency.

Applicable to ports listed above and intended to connect to cables longer than 3 m.

NOTE:

(1) The test result calculated as following:

Measurement Value = Reading Level + Correct Factor

Correct Factor = Insertion Loss + Cable Loss + Attenuator Factor(if use)

Margin Level = Measurement Value – Limit Value

3.3.2 MEASUREMENT INSTRUMENTS LIST

Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated until
1	Measurement Software	Farad	EZ-EMC Ver.NB-03A1-01	N/A	N/A
2	50Ω Terminator	SHX	TF2-3G-A	08122901	Mar. 26, 2018
3	TWO-LINE V-NETWORK	R&S	ENV216	100526	Mar. 26, 2018
4	EMI Test Receiver	R&S	ESR3	101862	Aug. 15, 2018
5	Artificial-Mains Network	SCHWARZBECK	NSLK 8127	8127685	Aug. 20, 2018
6	Cable	N/A	RG400 12m	N/A	Mar. 07, 2018
7	ISN	Teseq GmbH	ISN T8	30833	Aug. 20, 2018

Remark: "N/A" denotes no model name, no serial No. or no calibration specified.

All calibration period of equipment list is one year.

3.3.3 TEST PROCEDURE

- The EUT was placed 0.8 meters from the horizontal ground plane with EUT being connected to the power mains through a line impedance stabilization network (LISN). All other support equipment powered from additional LISN(s). The LISN provide 50 Ohm/ 50uH of coupling impedance for the measuring instrument.
- Interconnecting cables that hang closer than 40 cm to the ground plane shall be folded back and forth in the center forming a bundle 30 to 40 cm long.
- I/O cables that are not connected to a peripheral shall be bundled in the center. The end of the cable may be terminated, if required, using the correct terminating impedance. The overall length shall not exceed 1 m.
- For the actual test configuration, please refer to the related Item –EUT Test Photos.
- AAN, CP or CVP** at least 80 cm from nearest part of EUT chassis.

NOTE:


- The communication function of EUT was executed and AAN was connected between EUT and associated equipment and the AAN was connected directly to reference ground plane.
Measure the voltage at the measurement port of the AAN
Correct the measured voltage by adding the AAN voltage division factor
Compare the corrected voltage with the limit(**For AAN**)
- Measure the current with a current probe and compare to the current limit(**For CP**)
- The current shall be measured with the current probe and the results compared with the current limits.
The voltage measured shall be corrected at each frequency of interest as follows:
 - if the current margin with respect to the current limit is ≤ 6 dB, the actual current margin shall be subtracted from the measured voltage;
 - if the current margin with respect to the current limit is >6 dB, 6 dB shall be subtracted from the measured voltage.
 The adjusted voltage shall be compared with the applicable voltage limit.
Both the measured current and the corrected voltage shall be below the applicable current and voltage limits at all frequencies for the EUT to be deemed compliant with this publication.(**For CVP**)

3.3.4 DEVIATION FROM TEST STANDARD


No deviation

3.3.5 TEST SETUP


a) Cable Type: Balanced Unscreened, Screened or Coaxial



b) Cable Type: Screened or Coaxial




c) Cable Type: Balanced Unscreened, Unbalanced




3.3.6 TEST RESULTS

EUT	IP Phone	Model Name	XT-22G
Temperature	25°C	Relative Humidity	53%
Test Voltage	AC 230V/50Hz		
Test Mode	PC Port 1Gbps		
Note	Adapter		
Test Engineer	Simon Ling		




No.	Freq. MHz	Reading Level dBuV	Correct Factor dB	Measure ment dBuV	Limit dBuV	Margin dB	Detector
1 *	0.4605	49.87	10.18	60.05	74.68	-14.63	QP
2	0.4605	39.50	10.18	49.68	64.68	-15.00	AVG
3	0.6809	41.44	10.15	51.59	74.00	-22.41	QP
4	0.6809	30.60	10.15	40.75	64.00	-23.25	AVG
5	1.5765	41.93	10.12	52.05	74.00	-21.95	QP
6	1.5765	31.20	10.12	41.32	64.00	-22.68	AVG
7	2.3685	40.97	10.13	51.10	74.00	-22.90	QP
8	2.3685	30.31	10.13	40.44	64.00	-23.56	AVG
9	24.3150	42.70	10.88	53.58	74.00	-20.42	QP
10	24.3150	32.80	10.88	43.68	64.00	-20.32	AVG
11	29.5350	43.25	11.10	54.35	74.00	-19.65	QP
12	29.5350	32.10	11.10	43.20	64.00	-20.80	AVG

EUT	IP Phone	Model Name	XT-22G
Temperature	25°C	Relative Humidity	53%
Test Voltage	AC 230V/50Hz		
Test Mode	PC Port 100Mbps		
Note	Adapter		
Test Engineer	Simon Ling		




No.	Freq. MHz	Reading Level dBuV	Correct Factor dB	Measure ment dBuV	Limit dBuV	Margin dB	Detector
1	0.4515	50.20	10.19	60.39	74.85	-14.46	QP
2 *	0.4515	40.30	10.19	50.49	64.85	-14.36	AVG
3	0.7215	41.47	10.14	51.61	74.00	-22.39	QP
4	0.7215	31.70	10.14	41.84	64.00	-22.16	AVG
5	1.5405	41.86	10.12	51.98	74.00	-22.02	QP
6	1.5405	31.90	10.12	42.02	64.00	-21.98	AVG
7	2.9310	41.13	10.15	51.28	74.00	-22.72	QP
8	2.9310	31.41	10.15	41.56	64.00	-22.44	AVG
9	13.0065	43.33	10.45	53.78	74.00	-20.22	QP
10	13.0065	32.21	10.45	42.66	64.00	-21.34	AVG
11	26.0160	44.13	10.95	55.08	74.00	-18.92	QP
12	26.0160	33.11	10.95	44.06	64.00	-19.94	AVG

EUT	IP Phone	Model Name	XT-22G
Temperature	25°C	Relative Humidity	53%
Test Voltage	AC 230V/50Hz		
Test Mode	PC Port 10Mbps		
Note	Adapter		
Test Engineer	Simon Ling		



No.	Freq. MHz	Reading Level dBuV	Correct Factor dB	Measure ment dBuV	Limit dBuV	Margin dB	Detector
1	0.4605	50.17	10.18	60.35	74.68	-14.33	QP
2	0.4605	40.20	10.18	50.38	64.68	-14.30	AVG
3	6.2520	47.02	10.26	57.28	74.00	-16.72	QP
4	6.2520	36.20	10.26	46.46	64.00	-17.54	AVG
5	8.7540	47.38	10.33	57.71	74.00	-16.29	QP
6	8.7540	36.50	10.33	46.83	64.00	-17.17	AVG
7 *	9.9960	54.27	10.37	64.64	74.00	-9.36	QP
8	9.9960	43.50	10.37	53.87	64.00	-10.13	AVG
9	11.2514	45.04	10.40	55.44	74.00	-18.56	QP
10	11.2514	34.31	10.40	44.71	64.00	-19.29	AVG
11	20.0040	47.61	10.69	58.30	74.00	-15.70	QP
12	20.0040	37.80	10.69	48.49	64.00	-15.51	AVG


EUT	IP Phone	Model Name	XT-22G
Temperature	25°C	Relative Humidity	53%
Test Voltage	DC 48V		
Test Mode	PC Port 10Mbps		
Note	POE		
Test Engineer	Simon Ling		



No.	Freq. MHz	Reading Level dBuV	Correct Factor dB	Measure ment dBuV	Limit dBuV	Margin dB	Detector
1	0.3300	54.80	10.25	65.05	77.45	-12.40	QP
2	0.3300	35.20	10.25	45.45	67.45	-22.00	AVG
3	0.8025	49.11	10.14	59.25	74.00	-14.75	QP
4	0.8025	38.60	10.14	48.74	64.00	-15.26	AVG
5	1.5990	49.85	10.12	59.97	74.00	-14.03	QP
6	1.5990	38.40	10.12	48.52	64.00	-15.48	AVG
7 *	10.0004	51.84	10.37	62.21	74.00	-11.79	QP
8	10.0004	41.30	10.37	51.67	64.00	-12.33	AVG
9	18.2445	47.82	10.63	58.45	74.00	-15.55	QP
10	18.2445	36.69	10.63	47.32	64.00	-16.68	AVG
11	21.6645	47.97	10.76	58.73	74.00	-15.27	QP
12	21.6645	37.10	10.76	47.86	64.00	-16.14	AVG


EUT	IP Phone	Model Name	XT-22G
Temperature	25°C	Relative Humidity	53%
Test Voltage	AC 230V/50Hz		
Test Mode	Internet Port 1Gbps		
Note	Adapter		
Test Engineer	Simon Ling		

100 dBuV




No.	Freq. MHz	Reading Level dBuV	Correct Factor dB	Measure ment dBuV	Limit dBuV	Margin dB	Detector
1	0.3209	49.86	10.26	60.12	77.68	-17.56	QP
2	0.3209	40.20	10.26	50.46	67.68	-17.22	AVG
3	0.4515	50.76	10.19	60.95	74.85	-13.90	QP
4 *	0.4515	41.20	10.19	51.39	64.85	-13.46	AVG
5	1.4460	44.95	10.12	55.07	74.00	-18.93	QP
6	1.4460	35.30	10.12	45.42	64.00	-18.58	AVG
7	1.9094	45.20	10.12	55.32	74.00	-18.68	QP
8	1.9094	36.10	10.12	46.22	64.00	-17.78	AVG
9	2.5305	43.96	10.14	54.10	74.00	-19.90	QP
10	2.5305	33.70	10.14	43.84	64.00	-20.16	AVG
11	3.7275	42.93	10.17	53.10	74.00	-20.90	QP
12	3.7275	31.60	10.17	41.77	64.00	-22.23	AVG

EUT	IP Phone	Model Name	XT-22G
Temperature	25°C	Relative Humidity	53%
Test Voltage	AC 230V/50Hz		
Test Mode	Internet Port 100Mbps		
Note	Adapter		
Test Engineer	Simon Ling		



No.	Freq. MHz	Reading Level dBuV	Correct Factor dB	Measure ment dBuV	Limit dBuV	Margin dB	Detector
1	0.3255	50.30	10.25	60.55	77.57	-17.02	QP
2	0.3255	41.20	10.25	51.45	67.57	-16.12	AVG
3	0.4560	51.65	10.18	61.83	74.77	-12.94	QP
4 *	0.4560	42.61	10.18	52.79	64.77	-11.98	AVG
5	1.3965	45.36	10.12	55.48	74.00	-18.52	QP
6	1.3965	35.80	10.12	45.92	64.00	-18.08	AVG
7	2.5350	45.43	10.14	55.57	74.00	-18.43	QP
8	2.5350	36.10	10.14	46.24	64.00	-17.76	AVG
9	19.3560	42.00	10.67	52.67	74.00	-21.33	QP
10	19.3560	31.90	10.67	42.57	64.00	-21.43	AVG
11	22.5330	41.30	10.80	52.10	74.00	-21.90	QP
12	22.5330	30.51	10.80	41.31	64.00	-22.69	AVG

EUT	IP Phone	Model Name	XT-22G
Temperature	25°C	Relative Humidity	53%
Test Voltage	AC 230V/50Hz		
Test Mode	Internet Port 10Mbps		
Note	Adapter		
Test Engineer	Simon Ling		



No.	Freq. MHz	Reading Level dBuV	Correct Factor dB	Measure ment dBuV	Limit dBuV	Margin dB	Detector
1	0.3209	44.87	10.26	55.13	77.68	-22.55	QP
2	0.3209	34.60	10.26	44.86	67.68	-22.82	AVG
3	0.4560	48.20	10.18	58.38	74.77	-16.39	QP
4	0.4560	37.31	10.18	47.49	64.77	-17.28	AVG
5	1.4190	42.09	10.12	52.21	74.00	-21.79	QP
6	1.4190	31.80	10.12	41.92	64.00	-22.08	AVG
7	3.6555	42.12	10.17	52.29	74.00	-21.71	QP
8	3.6555	31.60	10.17	41.77	64.00	-22.23	AVG
9 *	9.9960	51.95	10.37	62.32	74.00	-11.68	QP
10	9.9960	41.30	10.37	51.67	64.00	-12.33	AVG
11	29.8230	42.19	11.11	53.30	74.00	-20.70	QP
12	29.8230	32.31	11.11	43.42	64.00	-20.58	AVG

3.4 HARMONIC CURRENT EMISSIONS TEST

3.4.1 LIMITS

EN 61000-3-2						
Equipment Category	Harmonic Order	Max. Permissible Harmonic Current	Equipment Category	Harmonic Order	Max. Permissible Harmonic Current	
	n	A		n	A mA/w	
Class A	Odd Harmonics		Class D	Odd Harmonics only		
	3	2.30		3	2.30	3.4
	5	1.14		5	1.14	1.9
	7	0.77		7	0.77	1.0
	9	0.40		9	0.40	0.5
	11	0.33		11	0.33	0.35
	13	0.21		13	0.21	0.30
	15≤n≤39	0.15 x 15/n		15≤n≤39	0.15 x 15/n	3.85/n
	Even Harmonics					
	2	1.08				
	4	0.43				
	6	0.30				
	8≤n≤40	0.23 x 8/n				

3.4.2 MEASUREMENT INSTRUMENTS LIST

Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated until
1	Harmonics and Flicker Analyzer	California Instruments	PACS-1	72344	Aug. 15, 2018
2	3KVA AC Power source	California Instruments	3001ix	56309	Aug. 15, 2018
3	Measurement Software	California	CTS4.0 Version 4.9	N/A	N/A

Remark: "N/A" denotes no model name, no serial No. or no calibration specified.

All calibration period of equipment list is one year.


3.4.3 TEST PROCEDURE

- a. The EUT was placed on the top of a wooden table 0.8 meters above the ground and operated to produce the maximum harmonic components under normal operating conditions.
- b. The classification of EUT is according to of EN 61000-3-2. The EUT is classified as follows:
 - Class A: Balanced three-phase equipment, Household appliances excluding equipment as Class D, Tools excluding portable tools, Dimmers for incandescent lamps, audio equipment, equipment not specified in one of the three other classes.
 - Class B: Portable tools; Arc welding equipment which is not professional equipment.
 - Class C: Lighting equipment.
 - Class D: Equipment having a specified power less than or equal to 600 W of the following types: Personal computers and personal computer monitors and television receivers.
- c. The correspondent test program of test instrument to measure the current harmonics emanated from EUT is chosen. The measure time shall be not less than the time necessary for the EUT to be exercised.

3.4.4 DEVIATION FROM TEST STANDARD

No deviation


3.4.5 TEST SETUP




3.4.6 TEST RESULTS

Harmonic - Class A			
EUT	IP Phone	Model Name	XT-22G
Temperature	25°C	Relative Humidity	55%
Test Voltage	AC 230V/50Hz		
Test Mode	Headphone		

Current & voltage waveforms



Harmonics and Class A limit line European Limits



Test result: Pass Worst harmonic was #11 with 1.1% of the limit.

Current Test Result Summary (Run time)			
EUT	IP Phone	Model Name	XT-22G
Temperature	25°C	Relative Humidity	55%
Test Voltage	AC 230V/50Hz		
Test Mode	Headphone		

Highest parameter values during test:

V_RMS (Volts): 230.10

I_Peak (Amps): 0.125

I_Fund (Amps): 0.008

Power (Watts): 1.9

Frequency(Hz): 49.99

I_RMS (Amps): 0.020

Crest Factor: 6.825

Power Factor: 0.441

Harm#	Harms(avg)	100%Limit	%of Limit	Harms(max)	150%Limit	%of Limit	Status
2	0.001	1.080	N/A	0.001	1.620	N/A	Pass
3	0.008	2.300	0.3	0.009	3.450	0.3	Pass
4	0.001	0.430	N/A	0.001	0.645	N/A	Pass
5	0.007	1.140	0.6	0.008	1.710	0.5	Pass
6	0.000	0.300	N/A	0.000	0.450	N/A	Pass
7	0.006	0.770	0.8	0.007	1.155	0.6	Pass
8	0.000	0.230	N/A	0.000	0.345	N/A	Pass
9	0.006	0.400	1.5	0.006	0.600	1.0	Pass
10	0.000	0.184	N/A	0.000	0.276	N/A	Pass
11	0.005	0.330	1.5	0.005	0.495	1.1	Pass
12	0.000	0.153	N/A	0.000	0.230	N/A	Pass
13	0.004	0.210	N/A	0.004	0.315	N/A	Pass
14	0.000	0.131	N/A	0.000	0.197	N/A	Pass
15	0.003	0.150	N/A	0.004	0.225	N/A	Pass
16	0.000	0.115	N/A	0.000	0.173	N/A	Pass
17	0.003	0.132	N/A	0.003	0.198	N/A	Pass
18	0.000	0.102	N/A	0.000	0.153	N/A	Pass
19	0.002	0.118	N/A	0.002	0.178	N/A	Pass
20	0.000	0.092	N/A	0.000	0.138	N/A	Pass
21	0.001	0.107	N/A	0.001	0.161	N/A	Pass
22	0.000	0.084	N/A	0.000	0.125	N/A	Pass
23	0.001	0.098	N/A	0.001	0.147	N/A	Pass
24	0.000	0.077	N/A	0.000	0.115	N/A	Pass
25	0.001	0.090	N/A	0.001	0.135	N/A	Pass
26	0.000	0.071	N/A	0.000	0.107	N/A	Pass
27	0.000	0.083	N/A	0.000	0.125	N/A	Pass
28	0.000	0.066	N/A	0.000	0.099	N/A	Pass
29	0.000	0.078	N/A	0.000	0.116	N/A	Pass
30	0.000	0.061	N/A	0.000	0.092	N/A	Pass
31	0.000	0.073	N/A	0.001	0.109	N/A	Pass
32	0.000	0.058	N/A	0.000	0.086	N/A	Pass
33	0.000	0.068	N/A	0.000	0.102	N/A	Pass
34	0.000	0.054	N/A	0.000	0.081	N/A	Pass
35	0.000	0.064	N/A	0.000	0.096	N/A	Pass
36	0.000	0.051	N/A	0.000	0.077	N/A	Pass
37	0.000	0.061	N/A	0.000	0.091	N/A	Pass
38	0.000	0.048	N/A	0.000	0.073	N/A	Pass
39	0.000	0.058	N/A	0.000	0.087	N/A	Pass
40	0.000	0.046	N/A	0.000	0.069	N/A	Pass

Voltage Source Verification Data (Run time)			
EUT	IP Phone	Model Name	XT-22G
Temperature	25°C	Relative Humidity	55%
Test Voltage	AC 230V/50Hz		
Test Mode	Headphone		

Highest parameter values during test:

Voltage (Vrms):230.10

Frequency(Hz): 49.99

I_Peak (Amps):0.125

I_RMS (Amps): 0.020

I_Fund (Amps):0.008

Crest Factor: 6.825

Power (Watts): 1.9

Power Factor: 0.441

Harm#	Harmonics V-rms	Limit V-rms	% of Limit	Status
2	0.121	0.460	26.30	OK
3	0.500	2.070	24.17	OK
4	0.063	0.460	13.76	OK
5	0.061	0.920	6.61	OK
6	0.028	0.460	6.13	OK
7	0.021	0.690	3.09	OK
8	0.022	0.460	4.76	OK
9	0.019	0.460	4.14	OK
10	0.025	0.460	5.41	OK
11	0.019	0.230	8.39	OK
12	0.016	0.230	6.76	OK
13	0.014	0.230	6.24	OK
14	0.012	0.230	5.35	OK
15	0.017	0.230	7.19	OK
16	0.018	0.230	7.64	OK
17	0.015	0.230	6.38	OK
18	0.012	0.230	5.13	OK
19	0.011	0.230	4.82	OK
20	0.015	0.230	6.53	OK
21	0.009	0.230	3.91	OK
22	0.012	0.230	5.23	OK
23	0.013	0.230	5.85	OK
24	0.007	0.230	3.23	OK
25	0.010	0.230	4.17	OK
26	0.009	0.230	3.73	OK
27	0.006	0.230	2.44	OK
28	0.006	0.230	2.62	OK
29	0.009	0.230	4.11	OK
30	0.007	0.230	2.93	OK
31	0.008	0.230	3.54	OK
32	0.006	0.230	2.43	OK
33	0.005	0.230	2.35	OK
34	0.004	0.230	1.60	OK
35	0.005	0.230	2.16	OK
36	0.004	0.230	1.86	OK
37	0.008	0.230	3.61	OK
38	0.003	0.230	1.25	OK
39	0.005	0.230	2.07	OK
40	0.005	0.230	2.35	OK

3.5 VOLTAGE CHANGES, VOLTAGE FLUCTUATIONS AND FLICKER TEST

3.5.1 LIMITS

Tests	Limits	Descriptions
	EN 61000-3-3	
Pst	≤ 1.0 , $T_p = 10$ min.	Short Term Flicker Indicator
Plt	≤ 0.65 , $T_p = 2$ hr.	Long Term Flicker Indicator
dc	$\leq 3.3\%$	Relative Steady-State V-Chang
dmax	$\leq 4\%$	Maximum Relative V-change
d (t)	$\leq 3.3\%$ for > 500 ms	Relative V-change characteristic

3.5.2 MEASUREMENT INSTRUMENTS LIST

Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated until
1	Harmonics and Flicker Analyzer	California Instruments	PACS-1	72344	Aug. 15, 2018
2	3KVA AC Power source	California Instruments	3001ix	56309	Aug. 15, 2018
3	Measurement Software	California	CTS4.0 Version 4.9	N/A	N/A

Remark: "N/A" denotes no model name, no serial No. or no calibration specified.

All calibration period of equipment list is one year.


3.5.3 TEST PROCEDURE

- Tests was performed according to the Test Conditions/Assessment of Voltage Fluctuations specified in EN 61000-3-3 depend on which standard adopted for compliance measurement.
- All types of harmonic current and/or voltage fluctuation in this report are assessed by direct measurement using flicker-meter.

3.5.4 DEVIATION FROM TEST STANDARD

No deviation

3.5.5 TESTSETUP




3.5.6 TEST RESULTS


EUT	IP Phone	Model Name	XT-22G
Temperature	25°C	Relative Humidity	55%
Test Voltage	AC 230V/50Hz		
Test Mode	Headphone		

Psti and limit line

European Limits



Plt and limit line



Parameter values recorded during the test:

Vrms at the end of test (Volt): 229.99

Highest dt (%): 0.00

T-max (mS): 0

Highest dc (%): 0.00

Highest dmax (%): -0.05

Highest Pst (10 min. period): 0.277

Highest Plt (2 hr. period): 0.121

Test limit (%): N/A N/A

Test limit (mS): 500.0 Pass

Test limit (%): 3.30 Pass

Test limit (%): 4.00 Pass

Test limit: 1.000 Pass

Test limit: 0.650 Pass

4. EMC IMMUNITY TEST

4.1 STANDARD COMPLIANCE/SEVERITY LEVEL/CRITERIA

Tests Standard No.	Test Specification Level / Test Mode	Test Ports	Criteria
Electrostatic discharge EN 61000-4-2 (ESD)	±8 kV air discharge ±4 kV contact discharge (Direct Mode)	Enclosure	B
	±4kV HCP discharge ±4kV VCP discharge (Indirect Mode)	Enclosure	B
Radiated, radio-frequency, electromagnetic field immunity EN 61000-4-3 (RS)	80 MHz to 1000 MHz 3V/m(unmodulated, r.m.s), 1 kHz, 80%, AM modulated	Enclosure	A
Electrical fast transient/burst immunity EN 61000-4-4 (EFT/Burst)	±0.5kV(peak) 5/50ns Tr/Th 5kHz Repetition Frequency (100kHz Repetition Frequency for xDSL equipment)	Signal ports and telecommunication ports (Only applicable to cable length>3 m)	B
	±0.5kV(peak) 5/50ns Tr/Th 5kHz Repetition Frequency	DC Power Ports	B
	±1 kV(peak) 5/50ns Tr/Th 5kHz Repetition Frequency	AC Power Ports	B
Surge immunity EN 61000-4-5 (Surges)	±1 kV(peak) 10/700 Tr/Th µs(NOTE) (without primary protection)	Signal ports and telecommunication ports (applicable only to ports connect directly to outdoor cables)	C
	±4 kV(peak) 10/700 Tr/Th µs(NOTE) (with primary protectors fitted)		C
	±0.5 kV(peak) 1.2/50(8/20) Tr/Th µs	DC Power Ports (applicable only to ports connect directly to outdoor cables)	B
	±1 kV(peak) 1.2/50(8/20) Tr/Th µs (line to line)	AC Power Ports	B
	±2 kV(peak) 1.2/50(8/20) Tr/Th µs (line to earth or ground)		B

Immunity to conducted disturbances, induced by radio-frequency fields EN 61000-4-6 (Injected Current)	0.15 MHz to 80 MHz 3V(unmodulated, r.m.s), 1kHz 80%, AM 150Ω source impedance	Signal ports and telecommunication ports (Only applicable to cable length>3 m)	A
	0.15 MHz to 80 MHz 3V(unmodulated, r.m.s), 1kHz 80%, AM 150Ω source impedance	DC Power Ports	A
	0.15 MHz to 80 MHz 3V(unmodulated, r.m.s), 1kHz 80%, AM 150Ω source impedance	AC Power Ports	A
Power frequency magnetic field immunity EN 61000-4-8 (PFMF)	50 Hz or 60Hz, 1A/m(r.m.s) μs	Enclosure	A
Voltage dips, short interruptions and voltage variations immunity EN 61000-4-11 (Voltage Interruption/Dips)	Voltage reduction > 95% 0.5 period Voltage reduction 30% 25 periods Voltage reduction > 95% 250 periods	AC Power Ports	B C C

Note.

Where the coupling network for the 10/700 μs waveform affects the functioning of high speed data ports, the test shall be carried out using a 1,2/50 (8/20) μs waveform and appropriate coupling network.

4.2 GENERAL PERFORMANCE CRITERIA

According to **EN55024** standard, the general performance criteria as following:

Criterion A	<p>The equipment shall continue to operate as intended without operator intervention. No degradation of performance or loss of function is allowed below a performance level specified by the manufacturer when the equipment is used as intended. The performance level may be replaced by a permissible loss of performance.</p> <p>If the minimum performance level or the permissible performance loss is not specified by the manufacturer, then either of these may be derived from the product description and documentation, and by what the user product description and documentation, and by what the user may reasonably expect from the equipment if used as intended.</p>
Criterion B	<p>After the test, the equipment shall continue to operate as intended without operator Intervention. No degradation of performance or loss of function is allowed, after the application of the phenomenon below a performance level specified by the manufacturer, when the equipment is used as intended. The performance level may be replaced by a permissible loss of performance.</p> <p>During the test, degradation of performance is allowed. However, no change of operating state if stored data allowed to persist after the test. If the minimum performance level (or the permissible performance loss) is not specified by the manufacturer, then either of these may be derived from the product description and documentation, and by what the user may reasonably expect from the equipment if used as intended.</p>
Criterion C	<p>Loss of function is allowed, provided the function is self-recoverable, or can be restored by the operation of the controls by the user in accordance with the manufacturer's instructions.</p> <p>Functions, and/or information stored in non-volatile memory, or protected by a battery backup, shall not be lost.</p>

4.3 ELECTROSTATIC DISCHARGE IMMUNITY TEST (ESD)

4.3.1 TEST SPECIFICATION

Basic Standard	EN 61000-4-2
Discharge Impedance	330 ohm / 150 pF
Required Performance	B
Discharge Voltage	Air Discharge: ± 2 kV, ± 4 kV, ± 8 kV (Direct) Contact Discharge: ± 2 kV, ± 4 kV (Indirect)
Polarity	Positive & Negative
Number of Discharge	Air Discharge: min. 20 times at each test point Contact Discharge: min. 200 times in total
Discharge Mode	Single Discharge
Discharge Period	1 second minimum

4.3.2 MEASUREMENT INSTRUMENTS

Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated until
1	ESD Generator	TESEQ AG	NSG 437	450	Nov. 03, 2017

Remark: "N/A" denotes no model name, no serial No. or no calibration specified.

All calibration period of equipment list is one year.

4.3.3 TEST PROCEDURE

The test generator necessary to perform direct and indirect application of discharges to the EUT in the following manner:

- Contact discharge was applied to conductive surfaces (Direct) and coupling planes (Indirect) of the EUT.

During the test, it was performed with single discharges. For the single discharge time between successive single discharges was at least 1 second. The EUT shall be exposed to at least 200 discharges, 100 each at negative and positive polarity, at a minimum of four test points. One of the test points shall be subjected to at least 50 indirect discharges to the center of the front edge of the horizontal coupling plane. The remaining three test points shall each receive at least 50 direct contact discharges.

If no direct contact test points are available, then at least 200 indirect discharges shall be applied in the indirect mode. Test shall be performed at a maximum repetition rate of one discharge per second.

Vertical Coupling Plane (VCP):

The coupling plane, of dimensions 0.5m x 0.5m, is placed parallel to, and positioned at a distance 0.1m from, the EUT, with the Discharge Electrode touching the coupling plane.

The four faces of the EUT will be performed with electrostatic discharge.

Horizontal Coupling Plane (HCP):

The coupling plane is placed under to the EUT. The generator shall be positioned vertically at a distance of 0.1m from the EUT, with the Discharge Electrode touching the coupling plane.

The four faces of the EUT will be performed with electrostatic discharge.


- Air discharges at insulation surfaces of the EUT.

It was at least ten single discharges with positive and negative at the same selected point.

4.3.4 DEVIATION FROM TEST STANDARD

No deviation

4.3.5 TEST SETUP



Note:

TABLE-TOP EQUIPMENT

The configuration consisted of a wooden table 0.8 meters high standing on the Ground Reference Plane. The GRP consisted of a sheet of aluminum at least 0.25mm thick, and 2.5 meters square connected to the protective grounding system. A Horizontal Coupling Plane (1.6m x 0.8m) was placed on the table and attached to the GRP by means of a cable with 940k total impedance. The equipment under test was installed in a representative system as described in EN 61000-4-2, and its cables were placed on the HCP and isolated by an insulating support of 0.5mm thickness. A distance of 1-meter minimum was provided between the EUT and the walls of the laboratory and any other metallic structure.

FLOOR-STANDING EQUIPMENT

The equipment under test was installed in a representative system as described in EN 61000-4-2, and its cables were isolated from the Ground Reference Plane by an insulating support of 0.1-meter thickness. The GRP consisted of a sheet of aluminum that is at least 0.25mm thick, and 2.5meters square connected to the protective grounding system and extended at least 0.5 meters from the EUT on all sides.

4.3.6 TEST RESULTS

EUT	IP Phone	Model Name	XT-22G
Temperature	25°C	Relative Humidity	48%
Test Voltage	AC 230V/50Hz	Pressure	1010hPa
Test Mode	Headphone		


Mode	Air Discharge								Contact Discharge					
	2kV		4kV		8kV		- kV		2kV		4kV		- kV	
Location	P	N	P	N	P	N	P	N	P	N	P	N	P	N
1	A	A	A	A	A	A	-	-	-	-	-	-	-	-
2	A	A	A	A	A	A	-	-	-	-	-	-	-	-
3	A	A	A	A	A	A	-	-	-	-	-	-	-	-
4	A	A	A	A	A	A	-	-	-	-	-	-	-	-
5	A	A	A	A	A	A	-	-	-	-	-	-	-	-
6	A	A	A	A	A	A	-	-	-	-	-	-	-	-
7	A	A	A	A	A	A	-	-	-	-	-	-	-	-
8	A	A	A	A	A	A	-	-	-	-	-	-	-	-
Criteria	B						-		B				-	
Result	A						-		N/A				-	
Judgment	PASS						-		N/A				-	


Mode	HCP Contact Discharge						VCP Contact Discharge					
	2kV		4kV		- kV		2kV		4kV		- kV	
Location	P	N	P	N	P	N	P	N	P	N	P	N
1	A	A	A	A	-	-	A	A	A	A	-	-
2	A	A	A	A	-	-	A	A	A	A	-	-
3	A	A	A	A	-	-	A	A	A	A	-	-
4	A	A	A	A	-	-	A	A	A	A	-	-
Criteria	B						B					
Result	A						A					
Judgment	PASS						PASS					


Note:

- 1) P/N denotes the Positive/Negative polarity of the output voltage.
- 2) Test condition:
Direct/Indirect(HCP/VCP) discharges: Minimum 50 times (Positive/Negative) at eachpoint.
Air discharges: Minimum 20 times (Positive/Negative) at each point.
- 3) Test location(s) in which discharge (Air and contact discharge) to be applied illustrated by photos shown in next page(s)
- 4) The Indirect (HCP/VCP) discharges description of test point as following:
1.left side; 2.right side; 3.front side; 4.rear side.
- 5) N/A - denotes test is not applicable in this test report
- 6) Criterion A: No observation of any performance degradation.
- 7) Criterion B: Some degradation of performance is observed but the equipment continues to operate as intended.
- 8) Criterion C: Loss of functionality, but self-recoverable by user, without loss of information or settings.

PHOTO(S) SHOWN THE LOCATION(S) OF ESD EVALUATED







4.4 RADIATED, RADIO-FREQUENCY, ELECTROMAGNETIC FIELD IMMUNITY TEST (RS)

4.4.1 TEST SPECIFICATION

Basic Standard	EN 61000-4-3
Required Performance	A
Frequency Range	80 MHz - 1000 MHz
Field Strength	3 V/m(unmodulated, r.m.s)
Modulation	1 kHz Sine Wave, 80%, AM Modulation
Frequency Step	1% of fundamental
Polarity of Antenna	Horizontal and Vertical
Test Distance	3 m
Antenna Height	1.5 m
Dwell Time	at least 3 seconds

4.4.2 MEASUREMENT INSTRUMENTS

Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated until
1	Free-field 1/2" Microphone	B&K	4190-L-001	2913343	Jun. 21, 2018
2	Audio Test System	Audio precision	ATS-1ACCE SS	ATS1-45376	Mar. 26, 2018
3	Conditioning Amplifier	B&K	_2690__0F2	2723746	Jul. 03, 2018
4	Antenna	ETS	3142C	00047662	Mar. 26, 2018
5	Digital Signal Generator	HP	ESG-D3000 A	US36260188	Mar. 26, 2018
6	Power amplifier	MILMEGA	80RF1000-2 50	1064833	Aug. 20, 2020
7	Measurement Software	TOYO	IM5/RS Ver 3.8.050	N/A	N/A

Remark: "N/A" denotes no model name, no serial No. or no calibration specified.

All calibration period of equipment list is one year.

4.4.3 TEST PROCEDURE

The EUT and support equipment, which are placed on a table that is 0.8 meter above ground and the testing was performed in a fully-anechoic chamber.

The testing distance from antenna to the EUT was 3 meters.


The other condition as following manner:

- The field strength level was 3 V/m(unmodulated, r.m.s).
- The frequency range is swept from 80 MHz to 1000 MHz, with the signal 80%amplitude modulated with a 1 kHz sine wave. The rate of sweep did not exceed 1.5×10^{-3} decade/s. Where the frequency range is swept incrementally, the step size was 1% of fundamental.
- The dwell time at each frequency shall be not less than the time necessary for the EUT to be able to respond.
- The test was performed with the EUT exposed to both vertically and horizontally polarized fields on each of the four sides.

4.4.4 DEVIATION FROM TEST STANDARD

No deviation

4.4.5 TEST SETUP



Note:

TABLE-TOP EQUIPMENT

The EUT installed in a representative system as described in EN 61000-4-3 was placed on a non-conductive table 0.8 meters in height. The system under test was connected to the power and signal wire according to relevant installation instructions.

FLOOR-STANDING EQUIPMENT

The EUT installed in a representative system as described in EN 61000-4-3 was placed on a non-conductive wood support 0.1 meters in height. The system under test was connected to the power and signal wire according to relevant installation instructions.

4.4.6 TEST RESULTS

EUT	IP Phone	Model Name	XT-22G
Temperature	25°C	Relative Humidity	58%
Test Voltage	AC 230V/50Hz		
Test Mode	Headphone		

Frequency Range (MHz)	RF Field Position	R.F. Field Strength	Azimuth	Criterion	Result	Judgment
80 - 1000	H / V	3V (unmodulated, r.m.s) AM Modulated 1000Hz, 80%	0	A	A	PASS
			90			
			180			
			270			

Note:

- 1) P/N denotes the Positive/Negative polarity of the output voltage.
- 2) N/A - denotes test is not applicable in this test report.
- 3) Criterion A: No observation of any performance degradation.
- 4) Criterion B: Some degradation of performance is observed but the equipment continues to operate as intended.
- 5) Criterion C: Loss of functionality, but self-recoverable by user, without loss of information or settings.

4.5 ELECTRICAL FAST TRANSIENT/BURST IMMUNITY TEST (EFT/BURST)

4.5.1 TEST SPECIFICATION

Basic Standard	EN 61000-4-4
Required Performance	B
Test Voltage	Power Line: ± 1 kV Signal/Control Line: ± 0.5 kV
Polarity	Positive & Negative
Impulse Frequency	5 kHz: except for xDSL equipment 100 kHz: only for single lines of xDSL equipment.
Impulse Wave shape	5/50 ns
Burst Duration	15 ms
Burst Period	300 ms
Test Duration	Not less than 1 min.

4.5.2 MEASUREMENT INSTRUMENTS

Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated until
1	Capacitor Clamp	Thermo KeyTek	CCL	0502215	Feb. 24, 2018
2	THE MODULAR SOLUTION FOR 6 KV APPLICATIONS	Teseq	NSG 3060	1423	Aug. 20, 2018
3	Measurement Software	Teseq	Win 3000 Version 1.2.0	N/A	N/A

Remark: "N/A" denotes no model name, no serial No. or no calibration specified.

All calibration period of equipment list is one year.

4.5.3 TEST PROCEDURE

The EUT and support equipment(s) are placed on a table that is 0.8 meter high above a metal ground plane and should be located 0.1 m \pm 0.01m high above the Ground Reference Plane (1m*1m min. and 0.65mm thick min).



The other condition as following manner:

- The length of power cord between the coupling device and the EUT should not exceed 1 meter.
- Both positive and negative polarity discharges were applied.
- The duration time of each test sequential was 1 minute

4.5.4 DEVIATION FROM TEST STANDARD

No deviation

4.5.5 TEST SETUP



Note:

TABLE-TOP EQUIPMENT

The configuration consisted of a wooden table (0.8m high) standing on the Ground Reference Plane and should be located 0.1 m+/- 0.01m above the Ground Reference Plane. The GRP consisted of a sheet of aluminum (at least 0.25mm thick and 2.5m square) connected to the protective grounding system. A minimum distance of 0.5m was provided between the EUT and the walls of the laboratory or any other metallic structure.

FLOOR-STANDING EQUIPMENT

The EUT installed in a representative system as described in EN 61000-4-4 and its cables were isolated from the Ground Reference Plane by an insulating support that is 0.1-meter thick. The GRP consisted of a sheet of aluminum (at least 0.25mm thick and 2.5m square) connected to the protective grounding system.

4.5.6 TEST RESULTS

EUT	IP Phone	Model Name	XT-22G
Temperature	25°C	Relative Humidity	52%
Test Voltage	AC 230V/50Hz		
Test Mode	Headphone		

EUT Ports Tested		Polarity	Repetition Frequency	Test Level 1kV	Criterion	Result	Judgment
AC Power Port	Line (L)	+	5 kHz	A	B	A	PASS
		-	5 kHz	A			
	Neutral (N)	+	5 kHz	A	B	A	PASS
		-	5 kHz	A			
	Ground (PE)	+	5 kHz	-	B	N/A	N/A
		-	5 kHz	-			

EUT Ports Tested		Polarity	Repetition Frequency	Test Level 0.5 kV	Criterion	Result	Judgment
Signal/Data/ Control Port	PC Port	+	5 kHz	A	B	A	PASS
		-	5 kHz	A			
Signal/Data/ Control Port	Internet Port	+	5 kHz	A	B	A	PASS
		-	5 kHz	A			

Note:

- 1) P/N denotes the Positive/Negative polarity of the output voltage.
- 2) N/A - denotes test is not applicable in this test report
- 3) Criterion A: No observation of any performance degradation.
- 4) Criterion B: Some degradation of performance is observed but the equipment continues to operate as intended.
- 5) Criterion C: Loss of functionality, but self-recoverable by user, without loss of information or settings.

4.6 SURGE IMMUNITY TEST

4.6.1 TEST SPECIFICATION

Basic Standard	EN 61000-4-5
Required Performance	B
Wave-Shape	Combination Wave for power lines 1.2/50 us Open Circuit Voltage 8 /20 us Short Circuit Current
Test Voltage	Power Line: ± 0.5 kV, ± 1 kV
Surge Input/Output	L-N
Generator Source Impedance	2 ohm between networks
Polarity	Positive/Negative
Phase Angle:	AC Port: $0^\circ/90^\circ/180^\circ/270^\circ$
Pulse Repetition Rate	1 time / min. (maximum)
Number of Tests	5 positive and 5 negative at selected points

4.6.2 MEASUREMENT INSTRUMENTS

Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated until
1	Measurement Software	Teseq	Win 3000 Version 1.2.0	N/A	N/A
2	THE MODULAR SOLUTION FOR 6 KV APPLICATIONS	Teseq	NSG 3060	1423	Aug. 20, 2018

Remark: "N/A" denotes no model name, no serial No. or no calibration specified.

All calibration period of equipment list is one year.

4.6.3 TEST PROCEDURE

a. For EUT power supply:

The surge is to be applied to the EUT power supply terminals via the capacitive coupling network. Decoupling networks are required in order to avoid possible adverse effects on equipment not under test that may be powered by the same lines, and to provide sufficient decoupling impedance to the surge wave. The power cord between the EUT and the coupling/decoupling networks shall be 2 meters in length (or shorter).

b. For test applied to unshielded unsymmetrically operated interconnection lines of EUT :

The surge is applied to the lines via the capacitive coupling. The coupling /decoupling networks shall not influence the specified functional conditions of the EUT. The interconnection line between the EUT and the coupling/decoupling networks shall be 2 meters in length (or shorter).


c. For test applied to unshielded symmetrically operated interconnection /telecommunication lines of EUT :

The surge is applied to the lines via gas arrestors coupling. Test levels below the ignition point of the coupling arrestor cannot be specified. The interconnection line between the EUT and the coupling/decoupling networks shall be 2 meters in length (or shorter).

4.6.4 DEVIATION FROM TEST STANDARD

No deviation

4.6.5 TEST SETUP



4.6.6 TEST RESULTS

EUT	IP Phone	Model Name	XT-22G
Temperature	25°C	Relative Humidity	52%
Test Voltage	AC 230V/50Hz		
Test Mode	Headphone		

Wave Form EUT Ports Tested		1.2/50(8/20)Tr/Thµs						Criterion	Result	Judgment
		Polarity	Phase	Voltage						
				0.5kV	1kV	-- kV	-- kV			
AC	L – N (2 ohm)	+/-	0°	A	A	-	-	B	A	PASS
		+/-	90°	A	A	-	-			
		+/-	180°	A	A	-	-			
		+/-	270°	A	A	-	-			

Note:

- 1) Polarity and Numbers of Impulses: 5 Pst / Ngt at each tested mode
- 2) N/A - denotes test is not applicable in this Test Report
- 3) Criterion A: No observation of any performance degradation.
- 4) Criterion B: Some degradation of performance is observed but the equipment continues to operate as intended.
- 5) Criterion C: Loss of functionality, but self-recoverable by user, without loss of information or settings.

4.7 IMMUNITY TO CONDUCTED DISTURBANCES, INDUCED BY RADIO-FREQUENCY FIELDS TEST (CS)

4.7.1 TEST SPECIFICATION

Basic Standard	EN 61000-4-6
Required Performance	A
Frequency Range	0.15 MHz - 80 MHz
Field Strength	3 V (unmodulated, r.m.s.)
Modulation	1 kHz Sine Wave, 80%, AM Modulation
Frequency Step	1% of fundamental
Dwell Time	at least 3 seconds

4.7.2 MEASUREMENT INSTRUMENTS

Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated until
1	Conditioning Amplifier	B&K	_2690__0F2	2723746	Jul. 03, 2018
2	Audio Test System	Audio precision	ATS-1ACCE SS	ATS1-45376	Mar. 26, 2018
3	Power CDN	FCC	FCC-801-M2 /M3-16A	100270	Mar. 26, 2018
4	Power Amplifier	Teseq	CBA230M-0 80	T43748	Mar. 26, 2018
5	Signal Generator	HP	8648A	3636A02964	Mar. 26, 2018
6	Measurement Software	Farad	EZ-CS(V2.0. 1.2)	N/A	N/A
7	Signal Line CDN	FCC	F-090407-10 04-1	100518	Mar. 26, 2018

Remark: "N/A" denotes no model name, no serial No. or no calibration specified.

All calibration period of equipment list is one year.

4.7.3 TEST PROCEDURE

The EUT and support equipment, are placed on a table that is 0.8 meter above a metal ground plane measured 1m*1m min. and 0.65mm thick min.


The other condition as following manner:

- The field strength level was 3 V (unmodulated, r.m.s.)
- The frequency range is swept from 150 kHz to 80 MHz, with the signal 80%amplitude modulated with a 1 kHz sine wave. The rate of sweep did not exceed 1.5×10^{-3} decade/s. Where the frequency range is swept incrementally, the step size was 1% of fundamental.
- The dwell time at each frequency shall be not less than the time necessary for the EUT to be able to respond.

4.7.4 DEVIATION FROM TEST STANDARD

No deviation

4.7.5 TEST SETUP



NOTE:

FLOOR-STANDING EQUIPMENT

The equipment to be tested is placed on an insulating support of 0.1 meters height above a ground reference plane. All relevant cables shall be provided with the appropriate coupling and decoupling devices at a distance between 0.1 meters and 0.3 meters from the projected geometry of the EUT on the ground reference plane.

4.7.6 TEST RESULTS

EUT	IP Phone	Model Name	XT-22G
Temperature	25°C	Relative Humidity	54%
Test Voltage	AC 230V/50Hz		
Test Mode	Headphone		

Test Ports (Mode)	Freq.Range (MHz)	Field Strength	Criteria	Results	Judgment
Input/ Output AC.PowerPort	0.15 ---80	3V(unmodulated , r.m.s) AM Modulated 1000Hz, 80%	A	A	PASS
Input/ Output DC. PowerPort	0.15 --- 80		A	N/A	N/A
Signal Line (PC Port)	0.15 --- 80		A	A	PASS
Signal Line (Internet Port)	0.15 --- 80		A	A	PASS

Note:

- 1). N/A - denotes test is not applicable in this test report.
- 2) Criterion A: No observation of any performance degradation.
- 3) Criterion B: Some degradation of performance is observed but the equipment continues to operate as intended.
- 4) Criterion C: Loss of functionality, but self-recoverable by user, without loss of information or settings.

4.8 POWER FREQUENCY MAGNETIC FIELD IMMUNITY TEST (PFMF)

4.8.1 TEST SPECIFICATION

Basic Standard	EN 61000-4-8
Required Performance	A
Frequency Range	50/60 Hz
Field Strength	1 A/m
Observation Time	1 minute
Inductance Coil	Rectangular type, 1mx1m

4.8.2 MEASUREMENT INSTRUMENTS

Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated until
1	Magnetic Field test Generator	FCC	F-1000-4-8-G-125A	04032	Mar. 26, 2018
2	Magnetic Field immunity loop	Thermo KeyTek	F-1000-4-8/9/10-L-1M	04024	Mar. 26, 2018

Remark: "N/A" denotes no model name, no serial No. or no calibration specified.

All calibration period of equipment list is one year.

4.8.3 TEST PROCEDURE

The EUT and support equipment, are placed on a table that is 0.8 meter above a metal ground plane measured 1m*1m min. and 0.65mm thick min.


The other condition as following manner:

- The equipment cabinets shall be connected to the safety earth directly on the GRP via the earth terminal of the EUT.
- The cables supplied or recommended by the equipment manufacturer shall be used. 1 meter of all cables used shall be exposed to the magnetic field.

4.8.4 DEVIATION FROM TEST STANDARD

No deviation

4.8.5 TEST SETUP



Note:

TABLE-TOP EQUIPMENT

The equipment shall be subjected to the test magnetic field by using the induction coil of standard dimension (1 m x 1 m). The induction coil shall then be rotated by 90 degrees in order to expose the EUT to the test field with different orientations.

FLOOR-STANDING EQUIPMENT

The equipment shall be subjected to the test magnetic field by using induction coils of suitable dimensions. The test shall be repeated by moving and shifting the induction coils, in order to test the whole volume of the EUT for each orthogonal direction. The test shall be repeated with the coil shifted to different positions along the side of the EUT, in steps corresponding to 50 percent of the shortest side of the coil. The induction coil shall then be rotated by 90 degrees in order to expose the EUT to the test field with different orientations.

4.8.6 TEST RESULTS

EUT	IP Phone	Model Name	XT-22G
Temperature	25°C	Relative Humidity	52%
Test Voltage	AC 230V/50Hz		
Test Mode	Headphone		

50Hz

Test Mode	Test Level	Antenna aspect	Duration (s)	Criteria	Results	Judgment
Enclosure	1 A/m	X	60	A	A	PASS
Enclosure	1 A/m	Y	60	A	A	PASS
Enclosure	1 A/m	Z	60	A	A	PASS

60Hz

Test Mode	Test Level	Antenna aspect	Duration (s)	Criteria	Results	Judgment
Enclosure	1 A/m	X	60	A	A	PASS
Enclosure	1 A/m	Y	60	A	A	PASS
Enclosure	1 A/m	Z	60	A	A	PASS

Note:

- 1). N/A - denotes test is not applicable in this test report.
- 2) Criterion A: No observation of any performance degradation.
- 3) Criterion B: Some degradation of performance is observed but the equipment continues to operate as intended.
- 4) Criterion C: Loss of functionality, but self-recoverable by user, without loss of information or settings.

4.9 VOLTAGE DIPS, SHORT INTERRUPTIONS AND VOLTAGE VARIATIONS IMMUNITY TEST

4.9.1 TEST SPECIFICATION

Basic Standard	EN 61000-4-11
Required Performance	B (For >95% Voltage Dips) C (For 30% Voltage Dips) C (For >95% Voltage Interruptions)
Test Duration Time	Minimum three test events in sequence
Interval between Event	Minimum ten seconds
Phase Angle	0°/180°
Test Cycle	3 times

4.9.2 MEASUREMENT INSTRUMENTS

Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated until
1	THE MODULAR SOLUTION FOR 6 KV APPLICATIONS	Teseq	NSG 3060	1423	Aug. 20, 2018
2	Measurement Software	Teseq	Win 3000 Version 1.2.0	N/A	N/A

Remark: "N/A" denotes no model name, no serial No. or no calibration specified.

All calibration period of equipment list is one year.


4.9.3 TEST PROCEDURE

The EUT shall be tested for each selected combination of test levels and duration with a sequence of three dips/interruptions with intervals of 10 s minimum (between each test event). Each representative mode of operation shall be tested. Abrupt changes in supply voltage shall occur at zero crossings of the voltage waveform.

4.9.4 DEVIATION FROM TEST STANDARD

No deviation

4.9.5 TEST SETUP



4.9.6 TEST RESULTS

EUT	IP Phone	Model Name	XT-22G
Temperature	25°C	Relative Humidity	52%
Test Voltage	AC 230V/50Hz		
Test Mode	Headphone		

AC 100V/50Hz				
Voltage Reduction	Periods	Criteria	Results	Judgment
Voltage dip >95%	0.5	B	A	PASS
Voltage dip 30%	25	C	A	PASS
Interruption >95%	250	C	C	PASS

AC 230V/50Hz				
Voltage Reduction	Periods	Criteria	Results	Judgment
Voltage dip >95%	0.5	B	A	PASS
Voltage dip 30%	25	C	A	PASS
Interruption >95%	250	C	C	PASS

AC 240V/50Hz				
Voltage Reduction	Periods	Criteria	Results	Judgment
Voltage dip >95%	0.5	B	A	PASS
Voltage dip 30%	25	C	A	PASS
Interruption >95%	250	C	C	PASS



Note:

- 1). N/A - denotes test is not applicable in this test report.
- 2) Criterion A: No observation of any performance degradation.
- 3) Criterion B: Some degradation of performance is observed but the equipment continues to operate as intended.
- 4) Criterion C: Loss of functionality, but self-recoverable by user, without loss of information or settings.

5. EUT TEST PHOTO


Adapter

Radiated emissions up to 1 GHz





PoE

Radiated emissions up to 1 GHz




Adapter

Radiated emissions above 1 GHz



PoE

Radiated emissions above 1 GHz




Adapter

Conducted emissions AC mains power port




Adapter

Asymmetric mode conducted emissions_AAN



PoE

Asymmetric mode conducted emissions_AAN



End of Test Report